

Stormwater Drainage Report

Proposed Residential Development

Project Location:

136 East Street
South Hadley, Massachusetts 01075
(Map 35, Parcel 6)

Applicant & Property Owner:

136 East Street, LLC
c/o Gerald Coderre
383 Newton Street
South Hadley, Massachusetts 01075



RLA Project File No. 250511

September 30, 2025

R LEVESQUE ASSOCIATES, INC

A LAND PLANNING SERVICES COMPANY

40 School Street · South Hadley, MA 01085
p 413.568.0985 · f 413.568.0986 · www.rlaland.com



TABLE OF CONTENTS

SECTION	PAGE NO.
I. INTRODUCTION.....	1-1
2. SITE DESCRIPTION	2-2
2.1 Predevelopment Conditions.....	2-2
2.2 Resource Areas	2-2
2.2.1 Floodplain.....	2-2
2.2.2 Natural Heritage and Endangered Species Program	2-3
2.2.3 Aquifer Protection District.....	2-3
2.3 Soils	2-3
2.4 Post Development Conditions.....	2-4
3. STORMWATER MANAGEMENT SYSTEM	3-5
3.1 Drainage Calculations.....	3-5
3.1.1 Design Points.....	3-6
3.1.2 Pre-Development Hydrology.....	3-6
3.1.3 Post-Development Hydrology	3-6
3.1.4 Peak Discharge Rates.....	3-6
3.2 Hydraulic Analysis.....	3-7
3.3 MassDEP Stormwater Management Standards	3-7
3.4 Stormwater Best Management Practices.....	3-10
3.4.1 Proprietary Sedimentation Devices.....	3-10
3.4.2 Subsurface Infiltration Basin.....	3-10
3.5 Protection of Stormwater Best Management Practices during Construction.....	3-11
3.6 Inspection and Maintenance of Stormwater Best Management Practices.....	3-11
3.7 Illicit Discharge Compliance Statement	3-11
3.8 Low-Impact Development Alternatives Analysis Narrative	3-11
4. CONCLUSION	4-12

List of Tables

Table	Page No.
Table 2.4: Hydrologic Soil Group Classification	2-3
Table 3.1: Design Rainfall Data – Hampshire County	3-5
Table 3.1.4 Pre- and Post-Development Peak Discharge Rates.....	3-6

List of Figures

Figure

- Figure 1: Site Locus – USGS Map
- Figure 2: FEMA Flood Map
- Figure 3: NHESP Map
- Figure 4: Pre-Development Watershed Plan
- Figure 5: Post-Development Watershed Plan
- Figure 6: Inlet Area Plan

Appendices

- APPENDIX A: CHECKLIST FOR STORMWATER REPORT
- APPENDIX B: SOILS INFORMATION
- APPENDIX C: PRE- AND POST- DEVELOPMENT HYDROLOGIC ANALYSIS
(2, 10, & 100 YEAR STORM EVENTS)
- APPENDIX D: HYDRAULIC ANALYSIS
- APPENDIX E: MASSDEP CALCULATIONS
- APPENDIX F: CONSTRUCTION PERIOD EROSION CONTROL PLAN
- APPENDIX G: LONG-TERM OPERATION AND MAINTENANCE PLAN
- APPENDIX H: ILLICIT DISCHARGE COMPLIANCE STATEMENT
- APPENDIX I: LOW IMPACT DEVELOPMENT CONSIDERATIONS

I. INTRODUCTION

The applicant, 136 East Street, LLC, is proposing to construct a condominium community on a parcel identified as lot 35-6 in South Hadley, Massachusetts. The proposed project will include the construction of eight (8) new condominium buildings (six duplex condominium buildings and two single unit buildings), parking areas, and other associated site improvements. Under existing conditions, stormwater runoff from the project area sheet flows west to east toward bordering vegetated wetlands located on the parcel. The proposed development will generally maintain the existing drainage patterns of the site and direct treated stormwater towards the same design points as in pre-development conditions.

The proposed project involves the following:

1. Construction of six (6) duplex condominium buildings and two (2) single unit buildings (14 total units);
2. Construction of associated site improvements including access drive, driveways, and landscaping;
3. Installation of underground utilities to the new buildings including water, sewer, and electric/telecommunications;
4. Construction of a new stormwater management system including deep-sump hooded catch basins, proprietary sedimentation devices, a subsurface infiltration basin, and a detention basin.

The purpose of this report is to present information regarding the technical aspects of the stormwater management system for the proposed project. All work is intended to be in full compliance with the Town of South Hadley Stormwater Management Permit requirements as well as the Massachusetts Department of Environmental Protection Stormwater Management Handbook.

2. SITE DESCRIPTION

2.1 Predevelopment Conditions

The property to be developed is located at 136 East Street and is listed as Parcel 35-6 by the Town of South Hadley Assessor's Office. The property is zoned Residence A-1 (RA-1), as referenced from South Hadley GIS. The property is bounded to the north and south by residentially developed properties also zoned RA-1, to the west by East Street and to the east by the town line to Granby. The parcel to be developed is approximately 9.9 acres in size. Figure 1 – USGS Map illustrates the location of the project.

Reference in this report to the project "site" shall mean the area of proposed development. The subject parcel is bordered to the east by a perennial stream (Stony Brook) with bordering vegetated wetland resource areas and wooded upland area. The entirety of the proposed development is located on the western side of the resource areas and the remaining area shall remain undisturbed. The existing topography of the project site can be described as sloping down moderately from the frontage along East Street to the wetland on the western side of the project site. The existing elevations along the frontage with East street range from approximately elevation 246 at the northwesterly corner of the parcel to 241 at the southwesterly corner. From the frontage with East Street, the elevations slope down to approximately 222 at the edge of the bordering vegetated wetland. Stormwater runoff from this area generally follows the existing topography and ultimately reaches the bordering vegetated wetlands. Please refer to the existing conditions plan submitted herewith for more detailed topographical information and Figure 4 "Pre-Development Watershed Plan" for sub-catchment area boundaries.

2.2 Resource Areas

Portions of the proposed site improvements are located within jurisdictional buffer zone areas associated with bordering vegetated wetland (BVW) resource areas. Please refer to the Notice of Intent filing for additional buffer zone impact information.

2.2.1 Floodplain

R. Levesque Associates, Inc. performed due diligence research on the property in regard to FEMA flood zone mapping. As demonstrated by the most recent FEMA Flood Insurance Rate Maps, the eastern portion of the property is located within the 100-year flood zone. The 100-year flood zone elevation for the subject property is 219' based on said mapping. Based on NOAA LIDAR contours, the 100-year flood zone elevation is contained within the delineated BVW, see Figure 2 – FEMA FIRM Map. All proposed site improvements are located outside the floodplain areas.

2.2.2 Natural Heritage and Endangered Species Program

R. Levesque Associates, Inc. performed due diligence research on the property in regard to Natural Heritage and Endangered Species Program (NHESP) areas. The property is not located within an NHESP priority habitats of endangered species, see Figure 3 – NHESP Map.

2.2.3 Aquifer Protection District

R. Levesque Associates, Inc. performed due diligence research on the property in regard to wellhead protection overlay districts. The property is not located within a Zone II Wellhead Protection Area; see Figure 3 – NHESP & Zone II Map.

2.3 Soils

R. Levesque Associates, Inc. researched the soils located on site with information readily available by the United States Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS). Based on a review of the USDA Soil Survey of Hampshire County, Massachusetts, Central Part, the site is comprised of the following soil types:

Soil Description	Map Unit Symbol	Hydrologic Soil Group
Walpole sandy loam	31A	B
Swansea muck	51A	D
Sudbury fine sandy loam	260A	B
Agawam fine sandy loam	275A	B
Wethersfield fine sandy loam	397B	C

A total of nineteen (19) test pits were conducted by Ryan Nelson SE# 14394 to verify the existing site soil characteristics and evaluate the ability of the site to support the proposed stormwater drainage system components. The test pits were spread out across the site in anticipated infiltration areas to establish the elevation of the estimated seasonal high groundwater and soil conditions. Ground water was encountered in all of the test pits and varied in depth from 22 inches to 68 inches below grade. The depth of the test pits varied from 70 inches to 100 inches below grade. In general, the soil evaluations found the soil conditions to contain well drained sandy material with high groundwater elevations. See Appendix B for additional soils information.

2.4 Post Development Conditions

The proposed site improvements include a number of stormwater management features to properly meet the requirements set forth by the Town of South Hadley Stormwater Management Permit requirements. The proposed stormwater features include:

- Deep-Sump Hooded Catch Basins
- Proprietary sedimentation devices
- Subsurface infiltration basin
- Detention basin

The applicant is proposing to construct a condominium community on the subject property. The proposed development includes the construction of eight (8) new condominium buildings (14 total units), paved access drives with associated parking areas, and a stormwater management system. The new electric, sewer, and water services will be connected via the frontage with East Street.

The proposed stormwater management systems have been designed to attenuate stormwater runoff from storm events up to and including the 100-year 24-hr event on-site. The proposed stormwater management system will collect runoff from the impervious surfaces via sheet flow and inlet structures strategically located at low points across the site. The inlet structures include yard drains and deep-sump hooded catch basins. Once collected, the stormwater is then conveyed via underground infrastructure to proprietary sedimentation devices that will provide water quality treatment prior to reaching the subsurface infiltration basin. The subsurface infiltration basin has been designed to provide peak discharge rate attenuation and the required recharge volume for the project site to mitigate for the proposed site improvements. The subsurface basin is equipped with an outlet control structure that will discharge runoff towards the bordering vegetated wetlands to mimic the existing conditions of the site.

In addition to the subsurface infiltration basin, a small detention basin is being proposed adjacent to the northern property line. Stormwater runoff from behind the northerly units is collected via a swale where it is conveyed to the detention basin. The detention basin is necessary to provide peak discharge rate attenuation. The detention basin is equipped with an outlet control structure and directs discharge downgradient to the onsite wetlands.

Overall, the proposed site improvements will maintain the general drainage patterns of the site while improving water quality and reducing/maintaining peak discharge rates. See Figure 5 – Post-Development Watershed Plan for delineation of sub-catchment areas.

3. STORMWATER MANAGEMENT SYSTEM

R. Levesque Associates, Inc. has prepared the following drainage system calculations for the proposed project site. These calculations were performed to document compliance with the guidelines set forth by the Town of South Hadley Stormwater Management Permit requirements and the Massachusetts Department of Environmental Protection Stormwater Management Handbook (MassDEP Handbook). A detailed hydrologic analysis of the system was completed in order to evaluate the performance of the stormwater management system components, see Appendix C – Pre- and Post-Development Hydrologic Analysis. The proposed stormwater management system will collect runoff from on-site impervious areas and utilize stormwater best management practices to provide water quality treatment, groundwater recharge, and peak discharge rate attenuation.

3.1 Drainage Calculations

R. Levesque Associates, Inc. utilized the HydroCAD software program, developed by HydroCAD Software Solutions LLC, in order to create and analyze the site hydrology. The HydroCAD software is based upon the Soil Conservation Service (SCS) “Technical Release 20 – Urban Hydrology for Small Watersheds” and “Technical Release 55 – Urban Hydrology for small Watersheds” which are generally accepted industry standard methodologies. The analysis was conducted in order to establish the peak discharge rates and estimated run-off volume from the project site. This was accomplished to properly evaluate pre- and post-development conditions during various storm events. Contributing drainage areas were identified and soils, surface cover, watershed slope, and flow paths were evaluated to develop the necessary HydroCAD model input parameters.

Drainage calculations were performed for the Pre- and Post-Development conditions for the 24-hour, 2, 10, and 100-year Type III storm events. The total rainfall for each of the storm events was based upon data provided by the National Oceanic and Atmospheric Administration (NOAA) Atlas 14 point precipitation frequency estimates. The total rainfall values used in the hydrologic modeling for each event are shown in the following table:

Table 3.1: Design Rainfall Data – Hampshire County		
2-year, 24-hour storm	10-year, 24-hour storm	100-year, 24-hour storm
3.08 inches	4.97 inches	7.96 inches

3.1.1 Design Points

In order to compare the difference between pre- and post-development peak flows, existing and proposed watersheds were delineated. One Design Points (DP) was established with a flow path representing the longest time of concentration of run-off in each tributary watershed. For this analysis, the design point was determined as follows:

- DP-1 – Wetland: This design point represents runoff from the project area which is tributary to the onsite bordering vegetated wetland. Although not connected on the property, the two bordering vegetated wetland areas shown on the plans are tributary to the same general wetland system directly adjacent to the property.

3.1.2 Pre-Development Hydrology

The project area under existing conditions contains one (1) sub-catchment tributary to the design point described above. The sub-catchment was delineated based on the existing topography of the parcel and surrounding areas. The existing watershed area is shown on the attached Figure 4 entitled “Pre-Development Watershed Plan”. Peak discharge rates for the design point is depicted in Table 3.1.4.

3.1.3 Post-Development Hydrology

The project area under proposed conditions was broken down into four (4) sub-catchments discharging to the design point as described in existing conditions. The proposed watershed areas are shown on the attached Figure 5 entitled “Post-Development Watershed Plan”. Peak discharge rates for the design point are depicted in Table 3.1.4.

3.1.4 Peak Discharge Rates

The table below summarizes the Pre- and Post-Development peak discharge rates for each Design Point:

Table 3.1.4 Pre- and Post-Development Peak Discharge Rates						
	2-year storm (cfs)		10-year storm (cfs)		100-year storm (cfs)	
	Pre-	Post-	Pre-	Post-	Pre-	Post-
Design Point 1	0.4	0.4	3.2	3.1	10.6	9.5

As depicted in table 3.1.4, the post-development peak discharge rates do not increase over pre-development peak discharge rates for each of the storm events presented. This is accomplished by providing onsite attenuation through the proposed subsurface infiltration basin and surface detention basin.

3.2 Hydraulic Analysis

R. Levesque Associates, Inc. utilized the Hydraflow Storm Sewer Extension for AutoCAD Civil 3D 2012 software program, Version 9, developed by Autodesk, Inc., to analyze the hydraulic capacity of the proposed underground infrastructure. The analysis was conducted to verify that the proposed conveyance piping has sufficient capacity to convey up to and including the 24-hour, 100-year storm event. The data from the analysis was used to properly size the conveyance piping such that there is no or minimal surcharge of stormwater above the rim elevations within the paved areas. As part of the input parameters required for the hydraulic analysis, the tributary inlet areas were delineated based on topography, any additional connected discharges, characteristic land use coverages and flow paths, see Figure 6 – Inlet Area Plan. A minimum Time of Concentration (Tc) of (6) minutes was used in the calculations. Please refer to Appendix D for the hydraulic analysis of the proposed stormwater management system.

3.3 MassDEP Stormwater Management Standards

R. Levesque Associates, Inc. has designed the proposed stormwater management system to be in compliance with the MassDEP Stormwater Management Standards. Chapter 1, Volume 3 of the MassDEP Handbook outlines specific calculations, and other information, that must be submitted with each report to document compliance. The following summary highlights elements of the proposed project and how they apply to each standard.

- *Standard #1 - No new stormwater conveyances (e.g., outfalls) may discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth.*

The proposed project provides best management practices designed to the guidelines of the MassDEP Handbook. Therefore, no new untreated stormwater is discharged.

- *Standard #2 – Stormwater management systems shall be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates. This Standard may be waived for discharges to land subject to coastal storm flowage as defined in 310 CMR 10.04.*

The proposed stormwater management system has been designed such that the post-development peak discharge rates do not exceed the pre-development peak discharge rates

for the 2-year, 10-year, and 100-year 24-hour storms. See Appendix C for the Hydrologic Analysis.

- *Standard #3 - Loss of annual recharge to groundwater shall be eliminated or minimized through the use of environmentally sensitive site design, low impact development techniques, stormwater BMPs, and good operation and maintenance. At a minimum, the annual recharge from the post-development site shall approximate the annual recharge from pre-development conditions based on soil type. This Standard is met when the stormwater management system is designed to infiltrate the required volume as determined in accordance with the Massachusetts Stormwater Handbook.*

The proposed subsurface infiltration basin has been designed with the capacity to infiltrate the required recharge volume for the tributary impervious areas. See Appendix E for the Required Recharge Volume Calculations.

- *Standard #4 – Stormwater management systems shall be designed to remove 80% of the average annual post-construction load of TSS. It is presumed that this standard is met when:*
 - a. Suitable practices for source control and pollution prevention are identified in a long term pollution prevention plan, and thereafter are implemented and maintained;*
 - b. Structural stormwater BMPs practices are sized to capture the required water quality volume determined in accordance with the Massachusetts Stormwater Handbook; and*
 - c. Pretreatment is provided in accordance with the Massachusetts Stormwater Handbook*

The proposed stormwater management system has been designed to provide the required total suspended solids treatment prior to discharge to the design point. Additionally, the treatment train has been designed to provide the required runoff pre-treatment prior to discharge to the subsurface infiltration basin. See Appendix E for the Water Quality and Total Suspended Solids Removal Calculations.

- *Standard #5 - For land uses with higher potential pollutant loads, source control and pollution prevention shall be implemented in accordance with the Massachusetts Stormwater Handbook to eliminate or reduce the discharge of stormwater runoff from such land uses to the maximum extent practicable. If through source control and/or pollution prevention all land uses with higher potential pollutant loads cannot be completely protected from exposure to rain, snow, snow melt, and stormwater runoff, the proponent shall use the specific structural stormwater BMPs determined by MassDEP to be suitable for such uses as provided in the Massachusetts Stormwater Handbook. Stormwater discharges from land uses with higher potential pollutant loads shall also comply with the requirements of the*

Massachusetts Clean Waters Act, M.G.L. c. 21, §§ 26-53 and the regulations promulgated thereunder at 314 CMR 3.00, 314 CMR 4.00 and 314 CMR 5.00.

This standard is not applicable.

- *Standard #6 – Stormwater discharges within the Zone II or Interim Wellhead Protection Area of a public water supply, and stormwater discharges near or to any other critical area, require the use of the specific source control and pollution prevention measures and the specific structural stormwater BMPs determined by MassDEP to be suitable for managing discharges to such areas, as provided in the Massachusetts Stormwater Handbook. A discharge is near a critical area if there is a strong likelihood of a significant impact occurring to said area, taking into account site-specific factors. Stormwater discharges to Outstanding Resource Waters and Special Resource Waters shall be removed and set back from the receiving water or wetland and receive the highest and best practical method of treatment. A "storm water discharge" as defined in 314 CMR 3.04(2)(a)1 or (b) to an Outstanding Resource Water or Special Resource Water shall comply with 314 CMR 3.00 and 314 CMR 4.00. Stormwater discharges to a Zone I or Zone A are prohibited unless essential to the operation of a public water supply.*

This standard is not applicable.

- *Standard #7 – A redevelopment project is required to meet the following Stormwater Management Standards only to the maximum extent practicable: Standard 2, Standard 3, and the pretreatment and structural BMPs requirements of Standards 4, 5, and 6. Existing stormwater discharges shall comply with Standard 1 only to the maximum extent practicable. A redevelopment project shall also comply with all other requirements of the Stormwater Management Standards and improve existing conditions.*

This standard is not applicable.

- *Standard #8 – A plan to control construction-related impacts including erosion, sedimentation and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention) shall be developed and implemented.*

A Construction Period Erosion Control Plan has been provided in Appendix F.

- *Standard #9 – A long-term operation and maintenance plan shall be developed and implemented to ensure that stormwater management systems function as designed.*

A Long-term Operation & Maintenance Plan has been provided in Appendix G.

- *Standard #10 - All illicit discharges to the stormwater management system are prohibited.*

An illicit discharge statement will be provided prior to discharge of stormwater to post-construction BMPs. See Appendix H for a copy of the Illicit Discharge Statement.

3.4 Stormwater Best Management Practices

The proposed stormwater management system was designed utilizing stormwater best management practices (BMP) as set forth by the MassDEP Handbook. The BMPs utilized as part of the stormwater management system include deep-sump hooded catch basins, proprietary sedimentation devices, a subsurface infiltration basin, and a detention basin. All the BMPs were designed to meet the requirements of the MassDEP Handbook and will provide water quality treatment, groundwater recharge, and peak rate attenuation in order to mitigate the impacts of the proposed site improvements. See Appendix E – MassDEP Calculations for the calculations required to document compliance. The following section provides a description of the best management practices (BMPs) being utilized on site.

3.4.1 Deep Sump Catch Basins

Deep-sump catch basins equipped with an oil/gas hoods are being utilized as structural pretreatment devices within the proposed stormwater management system. The catch basins will be constructed with a 4'-0" deep sumps to act as settling chambers and allow for adequate storage of collected sediments. Catch basins are typically first in the line of water quality treatment.

3.4.2 Proprietary Sedimentation Devices

Proprietary sedimentation devices are being utilized on site for the pretreatment of stormwater runoff, prior to conveyance to the subsurface basin described below. The stormwater management system is utilizing the proprietary treatment device in order to ensure that the required water quality treatment is being performed prior to discharge to the down gradient BMP.

3.4.3 Subsurface Infiltration Basin

Subsurface infiltration basins are well suited to provide groundwater recharge from watershed areas such as those associated with this project. The subsurface infiltration basin provides groundwater recharge by providing storage of runoff prior to discharge out of the system from the overflow device. The subsurface infiltration basin consists of underground stormwater chambers embedded in stone. The discharge is conveyed to the subsurface infiltration basins via up-gradient drainage infrastructure where it is detained to provide groundwater recharge. During larger storm events, overflow will discharge via the outlet control structure toward the design point.

3.4.4 Dry Detention Basin

Dry Detention basins are typically utilized for the short-term detention of stormwater runoff from watershed areas such as those associated with this project that allows for a controlled release of runoff to meet pre-development flow rates. The proposed dry detention basin has been designed to store the volume required to meet the peak rate attenuation requirements of standard 2. The tributary watershed consists of the yard area around and behind the three northernmost duplex units.

3.5 Protection of Stormwater Best Management Practices during Construction

Protection of the stormwater best management practices during construction will ensure the proper functioning of the stormwater management system and provide protection to the undisturbed areas until the site has been stabilized. Certain specific erosion and sedimentation controls and good practices to be performed by the site contractor have been documented in a Construction Period Erosion Control Plan. See Appendix F – Construction Period Erosion Control Plan.

3.6 Inspection and Maintenance of Stormwater Best Management Practices

Frequent maintenance of the stormwater best management practices is essential to ensuring that the stormwater management system will function properly long-term. The MassDEP provides guidelines for the regular inspection and maintenance of the proposed stormwater best management practices. A Long-Term Stormwater Operation and Maintenance Plan has been prepared which dictates the inspection frequency and maintenance operations for each BMP. See Appendix G – Long-Term Operation and Maintenance Plan.

3.7 Illicit Discharge Compliance Statement

RLA has prepared an Illicit Discharge Compliance Statement to document compliance with the Massachusetts Department of Environmental Protection Stormwater Management Handbook, see Appendix H.


3.8 Low-Impact Development Alternatives Analysis Narrative

RLA has prepared a Low-Impact Development Alternatives Analysis Narrative as part of the Stormwater Drainage Report, see Appendix I.

4. CONCLUSION

The proposed stormwater management system has been designed to mitigate the impacts of the proposed site improvements by providing control for runoff water quality and water quantity. Implementation of stormwater best management practices such as deep-sump hooded catch basins, proprietary sedimentation devices, a subsurface infiltration basin, and a surface detention basin allow for a stormwater drainage design that is in conformance with the criteria set forth in the Town of South Hadley Stormwater Management Permit requirements and the Massachusetts Department of Environmental Protection Stormwater Management Handbook.

Figure 1: Site Locus – USGS Map



RLA

R LEVESQUE ASSOCIATES, INC
 A Land Planning Services Company

40 School Street · P.O. Box 640 · Westfield, MA 01086
 ph: 413.568.0985 fax: 413.568.0986 rland.com

SITE LOCUS
 USGS MAP


136 East Street, LLC
 383 Newton Street
 South Hadley, MA 01075

"Deer Meadow Way"
 136 East Street
 South Hadley, MA 01075

JOB NO: 250511
 DATE: 9/29/25
 SCALE: AS NOTED

FIG-1

Figure 2: FEMA Flood Map



R LEVESQUE ASSOCIATES, INC

A Land Planning Services Company

40 School Street · P.O. Box 640 · Westfield, MA 01086
 ph: 413.568.0985 fax: 413.568.0986 rland.com

FEMA
 FLOOD MAP


136 East Street, LLC
 383 Newton Street
 South Hadley, MA 01075

"Deer Meadow Way"
 136 East Street
 South Hadley, MA 01075

JOB NO: 250511
 DATE: 9/29/25
 SCALE: AS NOTED

FIG-2


Figure 3: NHESP Map



SITE

NO ZONE II

NO NHESP BOUNDARY




RLA
R LEVESQUE ASSOCIATES, INC
 A Land Planning Services Company
 40 School Street · P.O. Box 640 · Westfield, MA 01086
 ph: 413.568.0985 fax: 413.568.0986 rland.com

NHESP &
 Zone II Map

136 East Street, LLC
 383 Newton Street
 South Hadley, MA 01075
 "Deer Meadow Way"
 136 East Street
 South Hadley, MA 01075

JOB NO: 250511
 DATE: 9/29/25
 SCALE: AS NOTED
FIG-3

Figure 4: Pre-Development Watershed Plan



R LEVESQUE ASSOCIATES, INC
 A Land Planning Services Company
 40 School Street · P.O. Box 640 · Westfield, MA 01086
 ph: 413.568.0985 fax: 413.568.0986 rland.com


**Pre-Development
 Watershed Plan**

"Deer Meadow Way"
 136 East Street
 South Hadley, MA 01075
 136 East St, LLC
 c/o Gerald Coderre
 383 Newton Street, South Hadley, MA 01075

JOB NO.: 250511
 DATE: 9/29/25
 SCALE: As Noted


FIG-4

Figure 5: Post-Development Watershed Plan



LEGEND

- TIME OF CONC. FLOW PATH
- SUBCATCHMENT NAME
- SUB WATERSHED
- SOIL BOUNDARY



R LEVESQUE ASSOCIATES, INC
 A Land Planning Services Company
 40 School Street · P.O. Box 640 · Westfield, MA 01086
 ph: 413.568.0985 fax: 413.568.0986 rland.com


**Post-Development
 Watershed Plan**

"Deer Meadow Way"
 136 East Street
 South Hadley, MA 01075
 136 East St, LLC
 c/o Gerald Coderre
 383 Newton Street, South Hadley, MA 01075

JOB NO.: 250511
 DATE: 9/29/25
 SCALE: As Noted

FIG-5

Figure 6: Inlet Area Plan



R LEVESQUE ASSOCIATES, INC
 A Land Planning Services Company
 40 School Street · P.O. Box 640 · Westfield, MA 01086
 ph: 413.568.0985 fax: 413.568.0986 rland.com

Inlet Area Plan

"Deer Meadow Way"
 136 East Street
 South Hadley, MA 01075
 136 East St, LLC
 c/o Gerald Coderre
 383 Newton Street, South Hadley, MA 01075

JOB NO.: 250511
 DATE: 9/29/25
 SCALE: As Noted

FIG-6


Appendix A: Checklist for Stormwater Report



Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.¹ This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.


Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature



[Handwritten Signature] *[Handwritten Date: 9/30/25]*

Signature and Date

Checklist

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

- New development
- Redevelopment
- Mix of New Development and Redevelopment



Checklist for Stormwater Report

Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- No disturbance to any Wetland Resource Areas
- Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- Reduced Impervious Area (Redevelopment Only)
- Minimizing disturbance to existing trees and shrubs
- LID Site Design Credit Requested:
 - Credit 1
 - Credit 2
 - Credit 3
- Use of "country drainage" versus curb and gutter conveyance and pipe
- Bioretention Cells (includes Rain Gardens)
- Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- Treebox Filter
- Water Quality Swale
- Grass Channel
- Green Roof
- Other (describe): Proprietary Sedimentation Devices, Subsurface Infiltration Basin

Standard 1: No New Untreated Discharges

- No new untreated discharges
- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist for Stormwater Report

Checklist (continued)

Standard 2: Peak Rate Attenuation

- Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

Standard 3: Recharge

- Soil Analysis provided.
- Required Recharge Volume calculation provided.
- Required Recharge volume reduced through use of the LID site Design Credits.
- Sizing the infiltration, BMPs is based on the following method: Check the method used.
 - Static
 - Simple Dynamic
 - Dynamic Field¹
- Runoff from all impervious areas at the site discharging to the infiltration BMP.
- Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
 - Site is comprised solely of C and D soils and/or bedrock at the land surface
 - M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
 - Solid Waste Landfill pursuant to 310 CMR 19.000
 - Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist for Stormwater Report

Checklist (continued)

Standard 3: Recharge (continued)

- The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
 - Provisions for storing materials and waste products inside or under cover;
 - Vehicle washing controls;
 - Requirements for routine inspections and maintenance of stormwater BMPs;
 - Spill prevention and response plans;
 - Provisions for maintenance of lawns, gardens, and other landscaped areas;
 - Requirements for storage and use of fertilizers, herbicides, and pesticides;
 - Pet waste management provisions;
 - Provisions for operation and management of septic systems;
 - Provisions for solid waste management;
 - Snow disposal and plowing plans relative to Wetland Resource Areas;
 - Winter Road Salt and/or Sand Use and Storage restrictions;
 - Street sweeping schedules;
 - Provisions for prevention of illicit discharges to the stormwater management system;
 - Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
 - Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
 - List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
 - Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
 - is within the Zone II or Interim Wellhead Protection Area
 - is near or to other critical areas
 - is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
 - involves runoff from land uses with higher potential pollutant loads.
 - The Required Water Quality Volume is reduced through use of the LID site Design Credits.
 - Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



Checklist for Stormwater Report

Checklist (continued)

Standard 4: Water Quality (continued)

- The BMP is sized (and calculations provided) based on:
 - The ½" or 1" Water Quality Volume or
 - The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- The NPDES Multi-Sector General Permit does **not** cover the land use.
- LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- All exposure has been eliminated.
- All exposure has **not** been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

Standard 6: Critical Areas

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- Critical areas and BMPs are identified in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
 - Limited Project
 - Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
 - Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
 - Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
 - Bike Path and/or Foot Path
 - Redevelopment Project
 - Redevelopment portion of mix of new and redevelopment.
- Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
 - Construction Period Operation and Maintenance Plan;
 - Names of Persons or Entity Responsible for Plan Compliance;
 - Construction Period Pollution Prevention Measures;
 - Erosion and Sedimentation Control Plan Drawings;
 - Detail drawings and specifications for erosion control BMPs, including sizing calculations;
 - Vegetation Planning;
 - Site Development Plan;
 - Construction Sequencing Plan;
 - Sequencing of Erosion and Sedimentation Controls;
 - Operation and Maintenance of Erosion and Sedimentation Controls;
 - Inspection Schedule;
 - Maintenance Schedule;
 - Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- The project is **not** covered by a NPDES Construction General Permit.
- The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

Standard 9: Operation and Maintenance Plan

- The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
 - Name of the stormwater management system owners;
 - Party responsible for operation and maintenance;
 - Schedule for implementation of routine and non-routine maintenance tasks;
 - Plan showing the location of all stormwater BMPs maintenance access areas;
 - Description and delineation of public safety features;
 - Estimated operation and maintenance budget; and
 - Operation and Maintenance Log Form.
- The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
 - A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
 - A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

Standard 10: Prohibition of Illicit Discharges

- The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- An Illicit Discharge Compliance Statement is attached;
- NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.

Appendix B: Soils Information

- NRCS Soils Report
- Soil Evaluation Logs



United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for Hampshire County, Massachusetts, Central Part



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	5
Soil Map	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	12
Map Unit Descriptions.....	12
Hampshire County, Massachusetts, Central Part.....	14
5A—Saco silt loam, frequently ponded, 0 to 2 percent slopes, frequently flooded.....	14
31A—Walpole sandy loam, 0 to 3 percent slopes.....	15
51A—Swansea muck, 0 to 1 percent slopes.....	16
260A—Sudbury fine sandy loam, 0 to 3 percent slopes.....	18
275A—Agawam fine sandy loam, 0 to 3 percent slopes.....	19
397B—Wethersfield fine sandy loam, 3 to 8 percent slopes.....	21
References	23

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.





































Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map



MAP LEGEND

Area of Interest (AOI)	 Area of Interest (AOI)	 Spoil Area
Soils	 Soil Map Unit Polygons	 Stony Spot
	 Soil Map Unit Lines	 Very Stony Spot
	 Soil Map Unit Points	 Wet Spot
Special Point Features	 Blowout	 Other
	 Borrow Pit	 Special Line Features
	 Clay Spot	Water Features
	 Closed Depression	 Streams and Canals
	 Gravel Pit	Transportation
	 Gravelly Spot	 Rails
	 Landfill	 Interstate Highways
	 Lava Flow	 US Routes
	 Marsh or swamp	 Major Roads
	 Mine or Quarry	 Local Roads
	 Miscellaneous Water	Background
	 Perennial Water	 Aerial Photography
	 Rock Outcrop	
	 Saline Spot	
	 Sandy Spot	
	 Severely Eroded Spot	
	 Sinkhole	
	 Slide or Slip	
	 Sodic Spot	

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Hampshire County, Massachusetts, Central Part
 Survey Area Data: Version 19, Aug 28, 2024

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Oct 15, 2020—Oct 31, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background

MAP LEGEND

MAP INFORMATION

imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
5A	Saco silt loam, frequently ponded, 0 to 2 percent slopes, frequently flooded	0.8	8.2%
31A	Walpole sandy loam, 0 to 3 percent slopes	3.1	31.5%
51A	Swansea muck, 0 to 1 percent slopes	1.9	19.4%
260A	Sudbury fine sandy loam, 0 to 3 percent slopes	2.1	21.4%
275A	Agawam fine sandy loam, 0 to 3 percent slopes	1.9	18.9%
397B	Wethersfield fine sandy loam, 3 to 8 percent slopes	0.1	0.6%
Totals for Area of Interest		9.9	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not

Custom Soil Resource Report

mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Hampshire County, Massachusetts, Central Part

5A—Saco silt loam, frequently ponded, 0 to 2 percent slopes, frequently flooded

Map Unit Setting

National map unit symbol: 2zvds
Elevation: 100 to 560 feet
Mean annual precipitation: 40 to 50 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 140 to 240 days
Farmland classification: Not prime farmland

Map Unit Composition

Saco and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Saco

Setting

Landform: Alluvial flats
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Coarse-silty alluvium

Typical profile

H1 - 0 to 12 inches: silt loam
H2 - 12 to 44 inches: silt loam
H3 - 44 to 60 inches: stratified fine sand to very fine sand to very fine sandy loam to silt loam

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Very poorly drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.60 to 2.00 in/hr)
Depth to water table: About 0 to 2 inches
Frequency of flooding: Frequent
Frequency of ponding: Frequent
Available water supply, 0 to 60 inches: High (about 10.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6w
Hydrologic Soil Group: B/D
Ecological site: F144AY016MA - Very Wet Low Floodplain
Hydric soil rating: Yes

Minor Components

Limerick

Percent of map unit: 10 percent
Landform: Alluvial flats

Custom Soil Resource Report

Hydric soil rating: Yes

Swansea

Percent of map unit: 5 percent

Landform: Bogs

Hydric soil rating: Yes

31A—Walpole sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2svkl

Elevation: 0 to 1,350 feet

Mean annual precipitation: 36 to 71 inches

Mean annual air temperature: 39 to 55 degrees F

Frost-free period: 140 to 250 days

Farmland classification: Not prime farmland

Map Unit Composition

Walpole and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Walpole

Setting

Landform: Depressions

Landform position (three-dimensional): Tread

Down-slope shape: Concave

Across-slope shape: Concave

Parent material: Sandy glaciofluvial deposits derived from igneous, metamorphic and sedimentary rock

Typical profile

Oe - 0 to 1 inches: mucky peat

A - 1 to 7 inches: sandy loam

Bg - 7 to 21 inches: sandy loam

BC - 21 to 25 inches: gravelly sandy loam

C - 25 to 65 inches: very gravelly sand

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Poorly drained

Runoff class: Negligible

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high
(0.14 to 14.17 in/hr)

Depth to water table: About 0 to 4 inches

Frequency of flooding: None

Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water supply, 0 to 60 inches: Moderate (about 6.4 inches)

Custom Soil Resource Report

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4w

Hydrologic Soil Group: B/D

Ecological site: F144AY028MA - Wet Outwash

Hydric soil rating: Yes

Minor Components

Scarboro

Percent of map unit: 10 percent

Landform: Depressions

Landform position (three-dimensional): Tread

Down-slope shape: Concave

Across-slope shape: Concave

Ecological site: F144AY031MA - Very Wet Outwash

Hydric soil rating: Yes

Sudbury

Percent of map unit: 10 percent

Landform: Outwash plains

Landform position (three-dimensional): Dip

Down-slope shape: Concave

Across-slope shape: Linear

Ecological site: F144AY027MA - Moist Sandy Outwash

Hydric soil rating: No

51A—Swansea muck, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: 2trl2

Elevation: 0 to 1,140 feet

Mean annual precipitation: 36 to 71 inches

Mean annual air temperature: 39 to 55 degrees F

Frost-free period: 140 to 240 days

Farmland classification: Not prime farmland

Map Unit Composition

Swansea and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Swansea

Setting

Landform: Bogs, swamps

Landform position (three-dimensional): Dip

Down-slope shape: Concave

Across-slope shape: Concave

Custom Soil Resource Report

Parent material: Highly decomposed organic material over loose sandy and gravelly glaciofluvial deposits

Typical profile

Oa1 - 0 to 24 inches: muck
Oa2 - 24 to 34 inches: muck
Cg - 34 to 79 inches: coarse sand

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Very poorly drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 14.17 in/hr)
Depth to water table: About 0 to 6 inches
Frequency of flooding: Rare
Frequency of ponding: Frequent
Available water supply, 0 to 60 inches: Very high (about 16.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 8w
Hydrologic Soil Group: B/D
Ecological site: F144AY043MA - Acidic Organic Wetlands
Hydric soil rating: Yes

Minor Components

Freetown

Percent of map unit: 10 percent
Landform: Bogs, swamps
Landform position (three-dimensional): Dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Whitman

Percent of map unit: 5 percent
Landform: Drainageways, depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Scarboro

Percent of map unit: 5 percent
Landform: Drainageways, depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope, tread, dip
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

260A—Sudbury fine sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9b1z
Elevation: 0 to 2,100 feet
Mean annual precipitation: 40 to 50 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 140 to 240 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Sudbury and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Sudbury

Setting

Landform: Outwash plains
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Friable loamy eolian deposits over loose sandy glaciofluvial deposits

Typical profile

H1 - 0 to 10 inches: fine sandy loam
H2 - 10 to 16 inches: fine sandy loam
H3 - 16 to 28 inches: gravelly loamy sand
H4 - 28 to 60 inches: stratified gravelly sand to very gravelly loamy sand

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Moderately well drained
Runoff class: Very low
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: About 18 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 4.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: B
Ecological site: F144AY027MA - Moist Sandy Outwash
Hydric soil rating: No

Minor Components

Merrimac

Percent of map unit: 5 percent
Hydric soil rating: No

Hinckley

Percent of map unit: 5 percent
Hydric soil rating: No

Walpole

Percent of map unit: 5 percent
Landform: Terraces
Hydric soil rating: Yes

275A—Agawam fine sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2tyqw
Elevation: 0 to 1,040 feet
Mean annual precipitation: 36 to 71 inches
Mean annual air temperature: 39 to 55 degrees F
Frost-free period: 140 to 250 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Agawam and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Agawam

Setting

Landform: Moraines, kames, kame terraces, outwash plains, outwash terraces
Landform position (two-dimensional): Backslope, shoulder, footslope, summit
Landform position (three-dimensional): Side slope, crest, tread, riser, rise, dip
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Coarse-loamy eolian deposits over sandy and gravelly glaciofluvial deposits derived from gneiss, granite, schist, and/or phyllite

Typical profile

Ap - 0 to 11 inches: fine sandy loam
Bw1 - 11 to 16 inches: fine sandy loam
Bw2 - 16 to 26 inches: fine sandy loam
2C1 - 26 to 39 inches: loamy fine sand
2C2 - 39 to 55 inches: loamy fine sand
2C3 - 55 to 65 inches: loamy sand

Properties and qualities

Slope: 0 to 3 percent

Custom Soil Resource Report

Depth to restrictive feature: 15 to 35 inches to strongly contrasting textural stratification

Drainage class: Well drained

Runoff class: Very low

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high (0.14 to 14.17 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Maximum salinity: Nonsaline (0.0 to 1.9 mmhos/cm)

Available water supply, 0 to 60 inches: Low (about 3.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2s

Hydrologic Soil Group: B

Ecological site: F145XY008MA - Dry Outwash

Hydric soil rating: No

Minor Components

Ninigret

Percent of map unit: 5 percent

Landform: Terraces

Down-slope shape: Linear

Across-slope shape: Concave

Hydric soil rating: No

Windsor

Percent of map unit: 4 percent

Landform: Dunes, deltas, outwash terraces, outwash plains

Landform position (three-dimensional): Tread, riser

Down-slope shape: Convex, linear

Across-slope shape: Convex, linear

Hydric soil rating: No

Walpole

Percent of map unit: 3 percent

Landform: Deltas, depressions, outwash terraces, depressions, outwash plains

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Tread, talf, dip

Down-slope shape: Concave

Across-slope shape: Concave

Hydric soil rating: Yes

Hinckley

Percent of map unit: 3 percent

Landform: Deltas, kames, eskers, outwash plains

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Nose slope, side slope, crest, head slope, rise

Down-slope shape: Convex

Across-slope shape: Convex, linear

Hydric soil rating: No

397B—Wethersfield fine sandy loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9b26
Elevation: 100 to 440 feet
Mean annual precipitation: 40 to 50 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 140 to 240 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Wethersfield and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wethersfield

Setting

Landform: Hills
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Crest
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Friable coarse-loamy eolian deposits over firm loamy basal till derived from sandstone and shale

Typical profile

H1 - 0 to 9 inches: fine sandy loam
H2 - 9 to 16 inches: fine sandy loam
H3 - 16 to 23 inches: loam
H4 - 23 to 26 inches: gravelly loam
H5 - 26 to 60 inches: very gravelly fine sandy loam

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 20 to 31 inches to densic material
Drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately high (0.00 to 0.20 in/hr)
Depth to water table: About 18 to 30 inches
Frequency of flooding: None
Frequency of ponding: None
Available water supply, 0 to 60 inches: Low (about 4.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Ecological site: F145XY012CT - Well Drained Dense Till Uplands

Custom Soil Resource Report

Hydric soil rating: No

Minor Components

Ridgebury

Percent of map unit: 5 percent

Landform: Depressions

Hydric soil rating: Yes

Woodbridge

Percent of map unit: 5 percent

Hydric soil rating: No

Paxton

Percent of map unit: 5 percent

Hydric soil rating: No

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

A. Facility Information

Heirs of Roland Pelissier
 Owner Name
 136 East Street
 Street Address
 South Hadley
 City
 MA
 State
 35-6
 Map/Lot #
 Zip Code

B. Site Information

- (Check one) New Construction Upgrade
- Soil Survey NRCS 31A Walpole Sandy loam, 0-3% slopes
 Source Soil Map Unit Soil Series
Depressions greater than 80" from surface
 Landform Soil Limitations
Sandy glaciofluvial deposits derived from igneous metamorphic and sedimentary rock
 Soil Parent material
- Surficial Geological Report _____
 Year Published/Source Map Unit
 Description of Geologic Map Unit:
- Flood Rate Insurance Map Within a regulatory floodway? Yes No
- Within a velocity zone? Yes No
- Within a Mapped Wetland Area? Yes No If yes, MassGIS Wetland Data Layer: _____
 Wetland Type
- Current Water Resource Conditions (USGS): _____ Range: Above Normal Normal Below Normal
 Month/Day/ Year
- Other references reviewed:
 (Zone II, IWPA, Zone A, EEA Data Portal, etc.) _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 1+2 Hole # 6-20-2025 Date 12 pm Time 75°F Sunny Weather _____ Latitude _____ Longitude
 1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) Red Maple, Cherry, Vines Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 2-3 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) Plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 26" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-10	A	SL	10YR 3/2	-	Cnc : Dpl:	-	-	-	granular	friable	
10-25	Bw	SL	10YR 5/3	-	Cnc : Dpl:	-	-	-	massive	"	
25-	C	fine sand	10YR 6/3	46"	Cnc : 10YR 5/4 Dpl:	10%	-	-	single grain	loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 3 6-20-2025 11:20 AM 75°F Sunny _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Woodland Red Maple, cherry, vines N/A _____
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) Plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >75 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 66" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-10	A	SL	10YR 3/2	-	-	-	-	-	granular	friable	
10-24	Bw	SL	10YR 5/4	-	-	-	-	-	massive	"	
24-78"	C	med sand	10YR 6/3	48"	-	20%	-	-	single grain	loose	weeping

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 5,4 Hole # 6-20-2025 Date 9 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) Red Maple, cherry, vines Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 1-2 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) Plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >50 feet
 Property Line >50 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 48" Depth to Weeping in Hole < Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	SL	10YR 3/2	-	Cnc : Dpl:	-	-	-	granular	friable	
12-20"	Bw	SL	10YR 5/4	-	Cnc : Dpl:	-	-	-	massive	"	
20-70"+	C	coarse sand	10YR 7/2	32"	Cnc : 10YR 5/6 Dpl: 10YR 6/1	10%	-	-	single grain	loose	weeping
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 8 Hole # 6-20-2025 Date 9:30 AM Time 70°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) Red maple, dogwood Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 1-2 Slope (%)

Description of Location: 136 East St, S. Hadley

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) Plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >50 feet

 Property Line >20 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 39" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	SL	10YR 3/2	-	Cnc : Dpl:	-	-	-	granular	friable	
12-24	Bw	SL	10YR 5/4	-	Cnc : Dpl:	-	-	-	massive	"	
24-71"	C	Coarse Sand	10YR 7/2	26"	Cnc : 10YR 5/6 Dpl: 10YR 6/1	25%	-	-	Single grain	loose	Weeping
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 9, 10 Hole# 6-20-2025 Date 9:50 AM Time 70°F Cloudy Weather _____ Latitude _____ Longitude

1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) _____ Vegetation none Surface Stones (e.g., cobbles, stones, boulders, etc.) _____ Slope (%) 1-2

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) Plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >20 feet Drinking Water Well _____ feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 72" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	SL	10YR 3/2	-	Cnc : Dpl:	-	-	-	Granular	Friable	
12-24	Bw	SL	10YR 5/4	-	Cnc : Dpl:	-	-	-	Massive	"	
24-91+	C	Coarse Sand	10YR 7/2	24"	Cnc : 10YR 5/6 Dpl: 10YR 6/1	25%	-	-	Single grain	loose	weeping
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 11/12 Hole # 6-20-2025 Date 10:45 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) bitters Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 1-2 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >75 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 48" Depth to Weeping in Hole - Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	SL	10YR 3/2	-	Cnc : Dpl:	-	-	-	granular	friable	
12-24	Bw	SL	10YR 5/4	-	Cnc : Dpl:	-	-	-	massive	"	
24-70"+	C	coarse sand	10YR 7/2	34"	Cnc : 10YR 5/6 Dpl: 10YR 6/1	10%	-	-	single grain	loose	weeping
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 13 Hole # 6-20-2025 Date 11 AM Time 75F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) red maple, dogwood, vines Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 1-2 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) Plain

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >75 feet
 Property Line >50 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 50" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	SL	10YR 3/2	-	Cnc : - Dpl: -	-	-	-	granular	friable	
12-24	Bw	SL	10YR 5/4	-	Cnc : - Dpl: -	-	-	-	massive	"	
24-70"	C	Coarse Sand	10YR 7/2	34"	Cnc : 10YR 5/6 Dpl: 10YR 6/1	25%	-	-	single grain	loose	Weeping
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

Ryan Nelson
Signature of Soil Evaluator

6-20-2025
Date

Ryan Nelson #14394
Typed or Printed Name of Soil Evaluator / License #

6/30/2025
Expiration Date of License

N/A
Name of Approving Authority Witness

Approving Authority

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with Percolation Test Form 12.

Field Diagrams: Use this area for field diagrams:

See attached sketch



Commonwealth of Massachusetts
City/Town of S. Hadley

Coderre - East Street

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 15 Hole # 7-18-2025 Date 8 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Woodland (e.g., woodland, agricultural field, vacant lot, etc.) Locust, cherry Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 3-5 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) BS

3. Distances from: Open Water Body >100 feet Drainage Way >50 feet Wetlands >100 feet
 Property Line >15 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 30" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	SL	10YR 3/2	-	Cnc : -	-	-	-	granular	very Friable	
				-	Dpl: -						
12-30	B _w	SL	10YR 5/4	22"	Cnc : 10YR 5/6	10%	-	-	massive	"	
					Dpl: 10YR 5/1						
30-80"	C _D	SL	7.5YR 5/3	-	Cnc : -	-	15	2	"	firm	loose in hand
					Dpl: -						
					Cnc : -						
					Dpl: -						
					Cnc : -						
					Dpl: -						
					Cnc : -						
					Dpl: -						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 16 Hole # 7-18-2025 Date 8:20 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude
 1. Land Use Overgrown farm (e.g., woodland, agricultural field, vacant lot, etc.) Locust, catalpa Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 2-3 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) BS

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >75 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 80" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-16	A	LS	10YR 3/2	-	Cnc : -	-	-	-	granular	Very friable	
				-	Dpl: -						
16-44	Bw	LS	10YR 5/4	-	Cnc : -	-	-	-	massive	"	
				-	Dpl: -						
44-100+	C	fine sand	10YR 6/4	66"	Cnc : 10YR 5/4	10%	-	-	Single grain	loose	
					Dpl: 10YR 6/2						
					Cnc :						
					Dpl:						
					Cnc :						
					Dpl:						
					Cnc :						
					Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 17 Hole # 7-18-2025 Date 8:40 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Overgrown farm (e.g., woodland, agricultural field, vacant lot, etc.) Herbaceous Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 1-2 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) BS

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 88" Depth to Weeping in Hole 100" Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-8	A	LS	10YR 3/2	-	Cnc : - Dpl: -	-	-	-	granular	Very Friable	
8-24	Bw	LS	10YR 5/4	-	Cnc : - Dpl: -	-	-	-	massive	"	
68-100"+	C	fine Sand	10YR 6/4	68"	Cnc : 10YR 5/4 Dpl: -	20%	-	-	Single grain	loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 18 Hole # 7-18-2025 Date 8:30 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Overgrown farm (e.g., woodland, agricultural field, vacant lot, etc.) Herbaceous Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 2-3 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) BS

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 86" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	LS	10YR 3/2	-	Cnc : - Dpl: -	-	-	-	granular	very friable	
12-34	Bw	LS	10YR 5/4	-	Cnc : - Dpl: -	-	-	-	massive	II	
34-100"	C	fine sand	10YR 6/4	50"	Cnc : 10YR 5/6 Dpl: 10YR 6/1	15%	-	-	single grain	loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 19 Hole # 7-18-2025 Date 9:30 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use Overgrown farm (e.g., woodland, agricultural field, vacant lot, etc.) Herbaceous Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 2-3 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) BS

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >50 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 64" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	LS	10YR 3/2	-	Cnc : - Dpl: -	-	-	-	granular	very friable	
12-40	Bw	LS	10YR 5/4	-	Cnc : - Dpl: -	-	-	-	massive	"	
40-80"	C	fine sand	10YR 7/2	40"	Cnc : 10YR 5/8 Dpl: 10YR 6/1	20%	-	-	single grain	loose	hole collapsing
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: heavy weeping



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 20 Hole # 7-18-2025 Date 9 AM Time 75°F Sunny Weather _____ Latitude _____ Longitude

1. Land Use overgrown farm (e.g., woodland, agricultural field, vacant lot, etc.) Herbaceous Vegetation N/A Surface Stones (e.g., cobbles, stones, boulders, etc.) 2-3 Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ Landform _____ Position on Landscape (SU, SH, BS, FS, TS, Plain) BS

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 76" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-10	A	LS	10YR 3/2	-	Cnc : - Dpl: -	-	-	-	granular	Very friable	
10-22	Bw	LS	10YR 5/4	-	Cnc : - Dpl: -	-	-	-	massive	"	
22-100"	C	Fine sand	10YR 6/4	52"	Cnc : 10YR 5/6 Dpl: 10YR 6/2	15%	-	-	Single grain	loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area)

Deep Observation Hole Number: 21 + 20A 7-18-2025 9:15 AM 75°F Sunny _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Woodland Cherry, maple N/A _____
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: _____

2. Soil Parent Material: _____ BS _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >50 feet
 Property Line >50 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: Yes No If Yes: Disturbed Soil/Fill Material Weathered/Fractured Rock Bedrock

5. Groundwater Observed: Yes No If yes: 91" Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-10	A	LS	10YR 3/2	-	Cnc : Dpl:	-	-	-	granular	Very friable	
10-32	Bw	LS	10YR 5/4	-	Cnc : Dpl:	-	-	-	massive	"	
32-100"	C	fine Sand	10YR 6/3	5 48"	Cnc : 10YR 5/4 Dpl: 10YR 6/1	10%	-	-	Single grain	loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes: _____

Appendix C: Pre- and Post- Development Hydrologic Analysis (2, 10, 100 Year Storm Events)



NOAA Atlas 14, Volume 10, Version 3
 Location name: South Hadley, Massachusetts,
 USA*

Latitude: 42.2435°, Longitude: -72.5582°

Elevation: 236 ft**

* source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.331 (0.255-0.421)	0.395 (0.305-0.504)	0.500 (0.385-0.640)	0.588 (0.449-0.758)	0.709 (0.525-0.958)	0.800 (0.581-1.11)	0.895 (0.631-1.29)	0.998 (0.671-1.48)	1.14 (0.741-1.76)	1.26 (0.797-1.99)
10-min	0.468 (0.361-0.597)	0.560 (0.431-0.714)	0.710 (0.546-0.909)	0.834 (0.637-1.08)	1.00 (0.744-1.36)	1.13 (0.822-1.57)	1.27 (0.894-1.82)	1.41 (0.950-2.10)	1.62 (1.05-2.50)	1.78 (1.13-2.82)
15-min	0.551 (0.425-0.702)	0.659 (0.508-0.840)	0.835 (0.641-1.07)	0.980 (0.749-1.26)	1.18 (0.875-1.60)	1.33 (0.968-1.84)	1.49 (1.05-2.14)	1.66 (1.12-2.47)	1.90 (1.23-2.94)	2.10 (1.33-3.31)
30-min	0.748 (0.577-0.953)	0.895 (0.690-1.14)	1.14 (0.871-1.45)	1.33 (1.02-1.72)	1.61 (1.19-2.17)	1.81 (1.32-2.51)	2.03 (1.43-2.92)	2.26 (1.52-3.36)	2.59 (1.68-4.00)	2.86 (1.81-4.51)
60-min	0.945 (0.729-1.20)	1.13 (0.872-1.44)	1.44 (1.10-1.84)	1.69 (1.29-2.17)	2.03 (1.50-2.75)	2.30 (1.67-3.18)	2.57 (1.81-3.69)	2.86 (1.92-4.25)	3.28 (2.12-5.06)	3.62 (2.29-5.71)
2-hr	1.20 (0.939-1.52)	1.44 (1.12-1.81)	1.81 (1.41-2.30)	2.12 (1.64-2.71)	2.56 (1.91-3.43)	2.88 (2.11-3.96)	3.22 (2.30-4.63)	3.62 (2.44-5.33)	4.20 (2.73-6.44)	4.68 (2.97-7.34)
3-hr	1.38 (1.08-1.73)	1.64 (1.29-2.07)	2.08 (1.63-2.63)	2.44 (1.90-3.10)	2.95 (2.22-3.95)	3.32 (2.45-4.56)	3.72 (2.68-5.36)	4.20 (2.84-6.16)	4.92 (3.20-7.52)	5.54 (3.52-8.66)
6-hr	1.71 (1.35-2.12)	2.07 (1.64-2.57)	2.66 (2.10-3.32)	3.15 (2.47-3.96)	3.83 (2.92-5.10)	4.32 (3.23-5.93)	4.87 (3.56-7.02)	5.56 (3.77-8.11)	6.63 (4.33-10.1)	7.58 (4.83-11.8)
12-hr	2.08 (1.66-2.56)	2.57 (2.06-3.17)	3.39 (2.70-4.19)	4.06 (3.22-5.06)	4.99 (3.84-6.62)	5.66 (4.28-7.74)	6.42 (4.74-9.25)	7.39 (5.04-10.7)	8.96 (5.87-13.5)	10.3 (6.62-16.0)
24-hr	2.45 (1.98-2.99)	3.08 (2.49-3.76)	4.11 (3.31-5.04)	4.97 (3.98-6.13)	6.15 (4.78-8.10)	7.00 (5.35-9.52)	7.96 (5.94-11.4)	9.22 (6.32-13.3)	11.3 (7.41-16.9)	13.1 (8.41-20.1)
2-day	2.82 (2.31-3.40)	3.55 (2.90-4.29)	4.74 (3.86-5.76)	5.74 (4.64-7.01)	7.10 (5.58-9.29)	8.10 (6.24-10.9)	9.21 (6.93-13.2)	10.7 (7.36-15.3)	13.1 (8.65-19.5)	15.3 (9.83-23.3)
3-day	3.08 (2.54-3.70)	3.87 (3.19-4.65)	5.16 (4.23-6.23)	6.24 (5.08-7.58)	7.71 (6.09-10.0)	8.78 (6.80-11.8)	9.99 (7.55-14.2)	11.6 (8.01-16.5)	14.2 (9.40-21.1)	16.6 (10.7-25.1)
4-day	3.31 (2.74-3.96)	4.15 (3.43-4.96)	5.51 (4.54-6.62)	6.64 (5.43-8.04)	8.20 (6.50-10.6)	9.34 (7.25-12.5)	10.6 (8.04-15.0)	12.3 (8.52-17.5)	15.1 (9.98-22.3)	17.5 (11.3-26.5)
7-day	3.94 (3.29-4.67)	4.87 (4.06-5.77)	6.38 (5.30-7.60)	7.64 (6.30-9.17)	9.37 (7.47-12.0)	10.6 (8.30-14.1)	12.0 (9.14-16.8)	13.9 (9.65-19.6)	16.8 (11.2-24.8)	19.5 (12.6-29.3)
10-day	4.57 (3.84-5.39)	5.54 (4.65-6.54)	7.14 (5.96-8.46)	8.46 (7.02-10.1)	10.3 (8.23-13.1)	11.6 (9.09-15.3)	13.1 (9.94-18.2)	15.0 (10.5-21.0)	18.0 (12.0-26.3)	20.6 (13.3-30.9)
20-day	6.56 (5.57-7.65)	7.59 (6.44-8.87)	9.29 (7.85-10.9)	10.7 (8.97-12.6)	12.6 (10.2-15.8)	14.1 (11.0-18.1)	15.6 (11.8-21.1)	17.4 (12.3-24.2)	20.1 (13.5-29.2)	22.4 (14.6-33.4)
30-day	8.23 (7.04-9.54)	9.30 (7.94-10.8)	11.0 (9.40-12.9)	12.5 (10.6-14.7)	14.5 (11.7-17.9)	16.0 (12.6-20.4)	17.6 (13.2-23.4)	19.3 (13.7-26.7)	21.7 (14.6-31.4)	23.7 (15.4-35.2)
45-day	10.3 (8.87-11.9)	11.4 (9.82-13.2)	13.3 (11.3-15.4)	14.8 (12.6-17.3)	16.9 (13.7-20.7)	18.5 (14.6-23.3)	20.1 (15.1-26.4)	21.7 (15.4-29.8)	23.9 (16.1-34.4)	25.5 (16.7-37.8)
60-day	12.0 (10.4-13.8)	13.2 (11.4-15.2)	15.1 (13.0-17.5)	16.7 (14.3-19.4)	18.9 (15.4-23.0)	20.6 (16.3-25.8)	22.3 (16.8-29.0)	23.9 (17.0-32.7)	25.9 (17.5-37.1)	27.3 (17.9-40.4)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).





Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based depth-duration-frequency (DDF) curves
 Latitude: 42.2435°, Longitude: -72.5582°



[Back to Top](#)

Maps & aerials

Small scale terrain



Large scale terrain



Large scale map




Large scale aerial




[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)




WETLAND



Subcat



Reach



Pond



Link

Routing Diagram for 250511 - PRE

Prepared by R Levesque Associates, Printed 9/30/2025
HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

250511 - PRE

Prepared by R Levesque Associates
HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Printed 9/30/2025

Page 2

Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	Type III 24-hr		Default	24.00	1	3.08	2
2	10-Year	Type III 24-hr		Default	24.00	1	4.97	2
3	100-Year	Type III 24-hr		Default	24.00	1	7.96	2

250511 - PRE

Prepared by R Levesque Associates

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.08"

Printed 9/30/2025

Page 3

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment ES-1:

Runoff Area=232,202 sf 0.43% Impervious Runoff Depth=0.24"
Flow Length=491' Tc=23.7 min CN=WQ Runoff=0.4 cfs 4,718 cf

Link DP-1: WETLAND

Inflow=0.4 cfs 4,718 cf
Primary=0.4 cfs 4,718 cf

Total Runoff Area = 232,202 sf Runoff Volume = 4,718 cf Average Runoff Depth = 0.24"
99.57% Pervious = 231,193 sf 0.43% Impervious = 1,009 sf

Summary for Subcatchment ES-1:

Runoff = 0.4 cfs @ 12.59 hrs, Volume= 4,718 cf, Depth= 0.24"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-Year Rainfall=3.08"

Area (sf)	CN	Description
11,300	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
216,925	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
232,202		Weighted Average
231,193	55	99.57% Pervious Area
1,009	98	0.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.8	100	0.0400	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.00"
6.9	391	0.0360	0.95		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.7	491	Total			

Subcatchment ES-1:

Hydrograph




Summary for Link DP-1: WETLAND

Inflow Area = 232,202 sf, 0.43% Impervious, Inflow Depth = 0.24" for 2-Year event
Inflow = 0.4 cfs @ 12.59 hrs, Volume= 4,718 cf
Primary = 0.4 cfs @ 12.59 hrs, Volume= 4,718 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs

Link DP-1: WETLAND

Hydrograph



250511 - PRE

Type III 24-hr 10-Year Rainfall=4.97"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 6

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment ES-1:

Runoff Area=232,202 sf 0.43% Impervious Runoff Depth=1.01"
Flow Length=491' Tc=23.7 min CN=WQ Runoff=3.2 cfs 19,620 cf

Link DP-1: WETLAND

Inflow=3.2 cfs 19,620 cf
Primary=3.2 cfs 19,620 cf

Total Runoff Area = 232,202 sf Runoff Volume = 19,620 cf Average Runoff Depth = 1.01"
99.57% Pervious = 231,193 sf 0.43% Impervious = 1,009 sf

Summary for Subcatchment ES-1:

Runoff = 3.2 cfs @ 12.40 hrs, Volume= 19,620 cf, Depth= 1.01"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Year Rainfall=4.97"

Area (sf)	CN	Description
11,300	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
216,925	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
232,202		Weighted Average
231,193	55	99.57% Pervious Area
1,009	98	0.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.8	100	0.0400	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.00"
6.9	391	0.0360	0.95		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.7	491	Total			

Subcatchment ES-1:

Hydrograph




Summary for Link DP-1: WETLAND

Inflow Area = 232,202 sf, 0.43% Impervious, Inflow Depth = 1.01" for 10-Year event
Inflow = 3.2 cfs @ 12.40 hrs, Volume= 19,620 cf
Primary = 3.2 cfs @ 12.40 hrs, Volume= 19,620 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs

Link DP-1: WETLAND

Hydrograph



250511 - PRE

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 9

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment ES-1:

Runoff Area=232,202 sf 0.43% Impervious Runoff Depth=2.83"
Flow Length=491' Tc=23.7 min CN=WQ Runoff=10.6 cfs 54,804 cf

Link DP-1: WETLAND

Inflow=10.6 cfs 54,804 cf
Primary=10.6 cfs 54,804 cf

Total Runoff Area = 232,202 sf Runoff Volume = 54,804 cf Average Runoff Depth = 2.83"
99.57% Pervious = 231,193 sf 0.43% Impervious = 1,009 sf

Summary for Subcatchment ES-1:

Runoff = 10.6 cfs @ 12.35 hrs, Volume= 54,804 cf, Depth= 2.83"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
11,300	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
216,925	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
232,202		Weighted Average
231,193	55	99.57% Pervious Area
1,009	98	0.43% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
16.8	100	0.0400	0.10		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.00"
6.9	391	0.0360	0.95		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.7	491	Total			

Subcatchment ES-1:

Hydrograph




Summary for Link DP-1: WETLAND



Inflow Area = 232,202 sf, 0.43% Impervious, Inflow Depth = 2.83" for 100-Year event
Inflow = 10.6 cfs @ 12.35 hrs, Volume= 54,804 cf
Primary = 10.6 cfs @ 12.35 hrs, Volume= 54,804 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs

Link DP-1: WETLAND

Hydrograph






Subcat



Reach



Pond



Link

250511 - POST

Prepared by R Levesque Associates
HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Printed 9/30/2025

Page 2

Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	Type III 24-hr		Default	24.00	1	3.08	2
2	10-Year	Type III 24-hr		Default	24.00	1	4.97	2
3	100-Year	Type III 24-hr		Default	24.00	1	7.96	2

250511 - POST

Prepared by R Levesque Associates

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.08"

Printed 9/30/2025

Page 3

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PS-1A: Runoff Area=29,240 sf 3.45% Impervious Runoff Depth=0.47"
Flow Length=234' Tc=15.7 min CN=WQ Runoff=0.2 cfs 1,139 cf

Subcatchment PS-1B: Runoff Area=76,702 sf 72.98% Impervious Runoff Depth=2.19"
Tc=6.0 min CN=WQ Runoff=3.9 cfs 13,969 cf

Subcatchment PS-1C: Runoff Area=16,271 sf 0.00% Impervious Runoff Depth=0.39"
Flow Length=340' Tc=20.4 min CN=WQ Runoff=0.1 cfs 531 cf

Subcatchment PS-1D: Runoff Area=109,989 sf 0.00% Impervious Runoff Depth=0.26"
Flow Length=371' Tc=7.8 min CN=WQ Runoff=0.3 cfs 2,401 cf

Pond 1P: Peak Elev=233.08' Storage=6,123 cf Inflow=3.9 cfs 13,969 cf
Discarded=0.2 cfs 13,825 cf Primary=0.0 cfs 144 cf Outflow=0.2 cfs 13,969 cf

Pond 2P: Peak Elev=226.27' Storage=198 cf Inflow=0.1 cfs 531 cf
Primary=0.0 cfs 524 cf Secondary=0.0 cfs 0 cf Outflow=0.0 cfs 524 cf

Link DP-1: WETLAND Inflow=0.4 cfs 4,208 cf
Primary=0.4 cfs 4,208 cf

Total Runoff Area = 232,202 sf Runoff Volume = 18,041 cf Average Runoff Depth = 0.93"
75.46% Pervious = 175,212 sf 24.54% Impervious = 56,990 sf

250511 - POST

Prepared by R Levesque Associates
 HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.08"

Printed 9/30/2025

Page 4

Summary for Subcatchment PS-1A:

Runoff = 0.2 cfs @ 12.28 hrs, Volume= 1,139 cf, Depth= 0.47"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-Year Rainfall=3.08"

Area (sf)	CN	Description
16,864	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
8,399	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
<hr/>		
29,240		Weighted Average
28,231	60	96.55% Pervious Area
1,009	98	3.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.7	100	0.0800	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.00"
3.0	134	0.0224	0.75		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.7	234	Total			

Subcatchment PS-1A:

Hydrograph



Summary for Subcatchment PS-1B:


Runoff = 3.9 cfs @ 12.09 hrs, Volume= 13,969 cf, Depth= 2.19"
 Routed to Pond 1P :

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-Year Rainfall=3.08"

Area (sf)	CN	Description
20,722	61	>75% Grass cover, Good, HSG B
27,201	98	Paved parking, HSG B
28,779	98	Roofs, HSG B
76,702		Weighted Average
20,722	61	27.02% Pervious Area
55,980	98	72.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PS-1B:



Summary for Subcatchment PS-1C:

Runoff = 0.1 cfs @ 12.43 hrs, Volume= 531 cf, Depth= 0.39"
 Routed to Pond 2P :


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-Year Rainfall=3.08"

Area (sf)	CN	Description
15,907	61	>75% Grass cover, Good, HSG B
364	55	Woods, Good, HSG B
16,271		Weighted Average
16,271	61	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
19.2	100	0.0300	0.09		Sheet Flow, Grass: Bermuda n= 0.410 P2= 3.00"
1.2	240	0.0458	3.45		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
20.4	340	Total			

Subcatchment PS-1C:

Hydrograph



250511 - POST

Summary for Subcatchment PS-1D:

Runoff = 0.3 cfs @ 12.34 hrs, Volume= 2,401 cf, Depth= 0.26"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-Year Rainfall=3.08"

Area (sf)	CN	Description
27,867	61	>75% Grass cover, Good, HSG B
0	98	Roofs, HSG B
82,121	55	Woods, Good, HSG B
109,989		Weighted Average
109,989	57	100.00% Pervious Area
0	98	0.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.3	100	0.0650	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.00"
1.5	271	0.0424	3.09		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
7.8	371	Total			

Subcatchment PS-1D:

Hydrograph



Summary for Pond 1P:

Inflow Area = 76,702 sf, 72.98% Impervious, Inflow Depth = 2.19" for 2-Year event
 Inflow = 3.9 cfs @ 12.09 hrs, Volume= 13,969 cf
 Outflow = 0.2 cfs @ 13.97 hrs, Volume= 13,969 cf, Atten= 94%, Lag= 112.9 min
 Discarded = 0.2 cfs @ 10.60 hrs, Volume= 13,825 cf
 Primary = 0.0 cfs @ 13.97 hrs, Volume= 144 cf
 Routed to Link DP-1 : WETLAND

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Peak Elev= 233.08' @ 13.97 hrs Surf.Area= 8,967 sf Storage= 6,123 cf

Plug-Flow detention time= 240.5 min calculated for 13,969 cf (100% of inflow)
 Center-of-Mass det. time= 240.4 min (1,005.6 - 765.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	232.00'	8,312 cf	68.00'W x 131.87'L x 3.75'H Field A 33,626 cf Overall - 12,845 cf Embedded = 20,781 cf x 40.0% Voids
#2A	232.50'	12,845 cf	ADS_StormTech SC-800 +Cap x 252 Inside #1 Effective Size= 45.0"W x 33.0"H => 7.11 sf x 7.12'L = 50.6 cf Overall Size= 51.0"W x 33.0"H x 7.55'L with 0.43' Overlap 252 Chambers in 14 Rows Cap Storage= 3.4 cf x 2 x 14 rows = 95.8 cf
		21,157 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	231.00'	12.0" Round Culvert L= 192.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 231.00' / 227.00' S= 0.0208 1' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	234.50'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Device 1	233.00'	3.0" W x 3.0" H Vert. Orifice C= 0.600 Limited to weir flow at low heads
#4	Discarded	232.00'	1.020 in/hr Exfiltration over Surface area Phase-In= 0.01'

Discarded OutFlow Max=0.2 cfs @ 10.60 hrs HW=232.04' (Free Discharge)
 ↳4=Exfiltration (Exfiltration Controls 0.2 cfs)

Primary OutFlow Max=0.0 cfs @ 13.97 hrs HW=233.08' (Free Discharge)
 ↳1=Culvert (Passes 0.0 cfs of 5.3 cfs potential flow)
 ↳2=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)
 ↳3=Orifice (Orifice Controls 0.0 cfs @ 0.88 fps)

Pond 1P: - Chamber Wizard Field A

Chamber Model = ADS_StormTech SC-800 +Cap (ADS StormTech® SC-800 with cap volume)

Effective Size= 45.0"W x 33.0"H => 7.11 sf x 7.12'L = 50.6 cf

Overall Size= 51.0"W x 33.0"H x 7.55'L with 0.43' Overlap

Cap Storage= 3.4 cf x 2 x 14 rows = 95.8 cf

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

18 Chambers/Row x 7.12' Long +0.88' Cap Length x 2 = 129.87' Row Length +12.0" End Stone x 2 = 131.87' Base Length

14 Rows x 51.0" Wide + 6.0" Spacing x 13 + 12.0" Side Stone x 2 = 68.00' Base Width

6.0" Stone Base + 33.0" Chamber Height + 6.0" Stone Cover = 3.75' Field Height

252 Chambers x 50.6 cf + 3.4 cf Cap Volume x 2 x 14 Rows = 12,845.0 cf Chamber Storage

33,626.0 cf Field - 12,845.0 cf Chambers = 20,781.0 cf Stone x 40.0% Voids = 8,312.4 cf Stone Storage

Chamber Storage + Stone Storage = 21,157.4 cf = 0.486 af


Overall Storage Efficiency = 62.9%

Overall System Size = 131.87' x 68.00' x 3.75'


252 Chambers

1,245.4 cy Field

769.7 cy Stone



Pond 1P:



Stage-Area-Storage for Pond 1P:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
232.00	8,967	0	234.65	8,967	16,615
232.05	8,967	179	234.70	8,967	16,891
232.10	8,967	359	234.75	8,967	17,160
232.15	8,967	538	234.80	8,967	17,423
232.20	8,967	717	234.85	8,967	17,678
232.25	8,967	897	234.90	8,967	17,923
232.30	8,967	1,076	234.95	8,967	18,157
232.35	8,967	1,255	235.00	8,967	18,379
232.40	8,967	1,435	235.05	8,967	18,590
232.45	8,967	1,614	235.10	8,967	18,793
232.50	8,967	1,793	235.15	8,967	18,990
232.55	8,967	2,176	235.20	8,967	19,180
232.60	8,967	2,557	235.25	8,967	19,364
232.65	8,967	2,938	235.30	8,967	19,543
232.70	8,967	3,317	235.35	8,967	19,723
232.75	8,967	3,695	235.40	8,967	19,902
232.80	8,967	4,072	235.45	8,967	20,081
232.85	8,967	4,448	235.50	8,967	20,261
232.90	8,967	4,822	235.55	8,967	20,440
232.95	8,967	5,195	235.60	8,967	20,619
233.00	8,967	5,567	235.65	8,967	20,799
233.05	8,967	5,937	235.70	8,967	20,978
233.10	8,967	6,306	235.75	8,967	21,157
233.15	8,967	6,673			
233.20	8,967	7,039			
233.25	8,967	7,403			
233.30	8,967	7,765			
233.35	8,967	8,125			
233.40	8,967	8,484			
233.45	8,967	8,841			
233.50	8,967	9,196			
233.55	8,967	9,549			
233.60	8,967	9,900			
233.65	8,967	10,248			
233.70	8,967	10,595			
233.75	8,967	10,939			
233.80	8,967	11,281			
233.85	8,967	11,620			
233.90	8,967	11,957			
233.95	8,967	12,291			
234.00	8,967	12,622			
234.05	8,967	12,950			
234.10	8,967	13,276			
234.15	8,967	13,598			
234.20	8,967	13,917			
234.25	8,967	14,233			
234.30	8,967	14,545			
234.35	8,967	14,854			
234.40	8,967	15,158			
234.45	8,967	15,459			
234.50	8,967	15,755			
234.55	8,967	16,047			
234.60	8,967	16,333			

Summary for Pond 2P:

Inflow Area = 16,271 sf, 0.00% Impervious, Inflow Depth = 0.39" for 2-Year event
 Inflow = 0.1 cfs @ 12.43 hrs, Volume= 531 cf
 Outflow = 0.0 cfs @ 15.66 hrs, Volume= 524 cf, Atten= 82%, Lag= 193.7 min
 Primary = 0.0 cfs @ 15.66 hrs, Volume= 524 cf
 Routed to Link DP-1 : WETLAND
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link DP-1 : WETLAND

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Peak Elev= 226.27' @ 15.66 hrs Surf.Area= 801 sf Storage= 198 cf

Plug-Flow detention time= 224.9 min calculated for 523 cf (98% of inflow)
 Center-of-Mass det. time= 218.2 min (1,151.9 - 933.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	226.00'	2,507 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
226.00	668	110.0	0	0	668	
227.00	1,221	151.0	931	931	1,529	
228.00	1,960	196.0	1,576	2,507	2,784	

Device	Routing	Invert	Outlet Devices
#1	Primary	226.00'	6.0" Round Culvert L= 100.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 226.00' / 225.00' S= 0.0100 ' S Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf
#2	Device 1	226.00'	1.0" Vert. Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	227.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#4	Device 1	227.50'	48.0" x 48.0" Horiz. Gate C= 0.600 Limited to weir flow at low heads
#5	Secondary	227.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


Primary OutFlow Max=0.0 cfs @ 15.66 hrs HW=226.27' (Free Discharge)

- ↑ 1=Culvert (Passes 0.0 cfs of 0.2 cfs potential flow)
- ↑ 2=Orifice (Orifice Controls 0.0 cfs @ 2.30 fps)
- ↑ 3=Sharp-Crested Rectangular Weir (Controls 0.0 cfs)
- ↑ 4=Gate (Controls 0.0 cfs)

Secondary OutFlow Max=0.0 cfs @ 0.00 hrs HW=226.00' (Free Discharge)

- ↑ 5=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 2P:



250511 - POST

Prepared by R Levesque Associates

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.08"

Printed 9/30/2025

Page 14

Stage-Area-Storage for Pond 2P:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
226.00	668	0	227.06	1,260	1,005
226.02	677	13	227.08	1,274	1,030
226.04	687	27	227.10	1,287	1,056
226.06	697	41	227.12	1,300	1,082
226.08	706	55	227.14	1,314	1,108
226.10	716	69	227.16	1,328	1,135
226.12	726	84	227.18	1,341	1,161
226.14	735	98	227.20	1,355	1,188
226.16	745	113	227.22	1,369	1,215
226.18	755	128	227.24	1,382	1,243
226.20	765	143	227.26	1,396	1,271
226.22	775	159	227.28	1,410	1,299
226.24	786	174	227.30	1,424	1,327
226.26	796	190	227.32	1,439	1,356
226.28	806	206	227.34	1,453	1,385
226.30	817	222	227.36	1,467	1,414
226.32	827	239	227.38	1,481	1,443
226.34	837	255	227.40	1,496	1,473
226.36	848	272	227.42	1,510	1,503
226.38	859	289	227.44	1,525	1,534
226.40	869	307	227.46	1,539	1,564
226.42	880	324	227.48	1,554	1,595
226.44	891	342	227.50	1,569	1,626
226.46	902	360	227.52	1,584	1,658
226.48	913	378	227.54	1,598	1,690
226.50	924	396	227.56	1,613	1,722
226.52	935	415	227.58	1,628	1,754
226.54	946	434	227.60	1,644	1,787
226.56	957	453	227.62	1,659	1,820
226.58	969	472	227.64	1,674	1,853
226.60	980	491	227.66	1,689	1,887
226.62	991	511	227.68	1,705	1,921
226.64	1,003	531	227.70	1,720	1,955
226.66	1,014	551	227.72	1,736	1,990
226.68	1,026	572	227.74	1,751	2,025
226.70	1,038	592	227.76	1,767	2,060
226.72	1,049	613	227.78	1,782	2,095
226.74	1,061	634	227.80	1,798	2,131
226.76	1,073	656	227.82	1,814	2,167
226.78	1,085	677	227.84	1,830	2,204
226.80	1,097	699	227.86	1,846	2,240
226.82	1,109	721	227.88	1,862	2,277
226.84	1,121	743	227.90	1,878	2,315
226.86	1,134	766	227.92	1,894	2,353
226.88	1,146	789	227.94	1,911	2,391
226.90	1,158	812	227.96	1,927	2,429
226.92	1,171	835	227.98	1,944	2,468
226.94	1,183	859	228.00	1,960	2,507
226.96	1,196	882			
226.98	1,208	906			
227.00	1,221	931			
227.02	1,234	955			
227.04	1,247	980			


Summary for Link DP-1: WETLAND

Inflow Area = 232,202 sf, 24.54% Impervious, Inflow Depth > 0.22" for 2-Year event
Inflow = 0.4 cfs @ 12.32 hrs, Volume= 4,208 cf
Primary = 0.4 cfs @ 12.32 hrs, Volume= 4,208 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs

Link DP-1: WETLAND

Hydrograph



250511 - POST

Type III 24-hr 10-Year Rainfall=4.97"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 16

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PS-1A: Runoff Area=29,240 sf 3.45% Impervious Runoff Depth=1.43"
Flow Length=234' Tc=15.7 min CN=WQ Runoff=0.7 cfs 3,477 cf

Subcatchment PS-1B: Runoff Area=76,702 sf 72.98% Impervious Runoff Depth=3.82"
Tc=6.0 min CN=WQ Runoff=6.8 cfs 24,414 cf

Subcatchment PS-1C: Runoff Area=16,271 sf 0.00% Impervious Runoff Depth=1.34"
Flow Length=340' Tc=20.4 min CN=WQ Runoff=0.4 cfs 1,820 cf

Subcatchment PS-1D: Runoff Area=109,989 sf 0.00% Impervious Runoff Depth=1.06"
Flow Length=371' Tc=7.8 min CN=WQ Runoff=2.4 cfs 9,742 cf

Pond 1P: Peak Elev=233.82' Storage=11,418 cf Inflow=6.8 cfs 24,414 cf
Discarded=0.2 cfs 18,639 cf Primary=0.3 cfs 5,775 cf Outflow=0.5 cfs 24,414 cf

Pond 2P: Peak Elev=227.01' Storage=942 cf Inflow=0.4 cfs 1,820 cf
Primary=0.0 cfs 1,764 cf Secondary=0.0 cfs 0 cf Outflow=0.0 cfs 1,764 cf

Link DP-1: WETLAND Inflow=3.1 cfs 20,758 cf
Primary=3.1 cfs 20,758 cf

Total Runoff Area = 232,202 sf Runoff Volume = 39,453 cf Average Runoff Depth = 2.04"
75.46% Pervious = 175,212 sf 24.54% Impervious = 56,990 sf

250511 - POST

Prepared by R Levesque Associates
 HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.97"

Printed 9/30/2025

Page 17

Summary for Subcatchment PS-1A:

Runoff = 0.7 cfs @ 12.24 hrs, Volume= 3,477 cf, Depth= 1.43"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Year Rainfall=4.97"

Area (sf)	CN	Description
16,864	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
8,399	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
29,240		Weighted Average
28,231	60	96.55% Pervious Area
1,009	98	3.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.7	100	0.0800	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.00"
3.0	134	0.0224	0.75		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.7	234	Total			

Subcatchment PS-1A:

Hydrograph



Summary for Subcatchment PS-1B:

Runoff = 6.8 cfs @ 12.09 hrs, Volume= 24,414 cf, Depth= 3.82"
 Routed to Pond 1P :


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Year Rainfall=4.97"

Area (sf)	CN	Description
20,722	61	>75% Grass cover, Good, HSG B
27,201	98	Paved parking, HSG B
28,779	98	Roofs, HSG B
76,702		Weighted Average
20,722	61	27.02% Pervious Area
55,980	98	72.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PS-1B:

Hydrograph



Summary for Subcatchment PS-1C:

Runoff = 0.4 cfs @ 12.32 hrs, Volume= 1,820 cf, Depth= 1.34"
 Routed to Pond 2P :


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Year Rainfall=4.97"

Area (sf)	CN	Description
15,907	61	>75% Grass cover, Good, HSG B
364	55	Woods, Good, HSG B
16,271		Weighted Average
16,271	61	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
19.2	100	0.0300	0.09		Sheet Flow, Grass: Bermuda n= 0.410 P2= 3.00"
1.2	240	0.0458	3.45		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
20.4	340	Total			

Subcatchment PS-1C:

Hydrograph



Summary for Subcatchment PS-1D:

Runoff = 2.4 cfs @ 12.14 hrs, Volume= 9,742 cf, Depth= 1.06"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Year Rainfall=4.97"

Area (sf)	CN	Description
27,867	61	>75% Grass cover, Good, HSG B
0	98	Roofs, HSG B
82,121	55	Woods, Good, HSG B
109,989		Weighted Average
109,989	57	100.00% Pervious Area
0	98	0.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.3	100	0.0650	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.00"
1.5	271	0.0424	3.09		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
7.8	371	Total			

Subcatchment PS-1D:

Hydrograph



Summary for Pond 1P:

Inflow Area = 76,702 sf, 72.98% Impervious, Inflow Depth = 3.82" for 10-Year event
 Inflow = 6.8 cfs @ 12.09 hrs, Volume= 24,414 cf
 Outflow = 0.5 cfs @ 13.60 hrs, Volume= 24,414 cf, Atten= 93%, Lag= 90.9 min
 Discarded = 0.2 cfs @ 9.05 hrs, Volume= 18,639 cf
 Primary = 0.3 cfs @ 13.60 hrs, Volume= 5,775 cf
 Routed to Link DP-1 : WETLAND

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Peak Elev= 233.82' @ 13.60 hrs Surf.Area= 8,967 sf Storage= 11,418 cf

Plug-Flow detention time= 295.1 min calculated for 24,380 cf (100% of inflow)
 Center-of-Mass det. time= 295.2 min (1,055.3 - 760.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	232.00'	8,312 cf	68.00'W x 131.87'L x 3.75'H Field A 33,626 cf Overall - 12,845 cf Embedded = 20,781 cf x 40.0% Voids
#2A	232.50'	12,845 cf	ADS_StormTech SC-800 +Cap x 252 Inside #1 Effective Size= 45.0"W x 33.0"H => 7.11 sf x 7.12'L = 50.6 cf Overall Size= 51.0"W x 33.0"H x 7.55'L with 0.43' Overlap 252 Chambers in 14 Rows Cap Storage= 3.4 cf x 2 x 14 rows = 95.8 cf
		21,157 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	231.00'	12.0" Round Culvert L= 192.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 231.00' / 227.00' S= 0.0208 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	234.50'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Device 1	233.00'	3.0" W x 3.0" H Vert. Orifice C= 0.600 Limited to weir flow at low heads
#4	Discarded	232.00'	1.020 in/hr Exfiltration over Surface area Phase-In= 0.01'

Discarded OutFlow Max=0.2 cfs @ 9.05 hrs HW=232.04' (Free Discharge)

↳ **4=Exfiltration** (Exfiltration Controls 0.2 cfs)

Primary OutFlow Max=0.3 cfs @ 13.60 hrs HW=233.82' (Free Discharge)

↳ **1=Culvert** (Passes 0.3 cfs of 5.7 cfs potential flow)
 ↳ **2=Sharp-Crested Rectangular Weir** (Controls 0.0 cfs)
 ↳ **3=Orifice** (Orifice Controls 0.3 cfs @ 4.01 fps)

Pond 1P: - Chamber Wizard Field A

Chamber Model = ADS_StormTech SC-800 +Cap (ADS StormTech® SC-800 with cap volume)

Effective Size= 45.0"W x 33.0"H => 7.11 sf x 7.12'L = 50.6 cf

Overall Size= 51.0"W x 33.0"H x 7.55'L with 0.43' Overlap

Cap Storage= 3.4 cf x 2 x 14 rows = 95.8 cf

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

18 Chambers/Row x 7.12' Long +0.88' Cap Length x 2 = 129.87' Row Length +12.0" End Stone x 2 = 131.87' Base Length

14 Rows x 51.0" Wide + 6.0" Spacing x 13 + 12.0" Side Stone x 2 = 68.00' Base Width

6.0" Stone Base + 33.0" Chamber Height + 6.0" Stone Cover = 3.75' Field Height

252 Chambers x 50.6 cf + 3.4 cf Cap Volume x 2 x 14 Rows = 12,845.0 cf Chamber Storage

33,626.0 cf Field - 12,845.0 cf Chambers = 20,781.0 cf Stone x 40.0% Voids = 8,312.4 cf Stone Storage

Chamber Storage + Stone Storage = 21,157.4 cf = 0.486 af


Overall Storage Efficiency = 62.9%

Overall System Size = 131.87' x 68.00' x 3.75'


252 Chambers

1,245.4 cy Field

769.7 cy Stone



Pond 1P:



Stage-Area-Storage for Pond 1P:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
232.00	8,967	0	234.65	8,967	16,615
232.05	8,967	179	234.70	8,967	16,891
232.10	8,967	359	234.75	8,967	17,160
232.15	8,967	538	234.80	8,967	17,423
232.20	8,967	717	234.85	8,967	17,678
232.25	8,967	897	234.90	8,967	17,923
232.30	8,967	1,076	234.95	8,967	18,157
232.35	8,967	1,255	235.00	8,967	18,379
232.40	8,967	1,435	235.05	8,967	18,590
232.45	8,967	1,614	235.10	8,967	18,793
232.50	8,967	1,793	235.15	8,967	18,990
232.55	8,967	2,176	235.20	8,967	19,180
232.60	8,967	2,557	235.25	8,967	19,364
232.65	8,967	2,938	235.30	8,967	19,543
232.70	8,967	3,317	235.35	8,967	19,723
232.75	8,967	3,695	235.40	8,967	19,902
232.80	8,967	4,072	235.45	8,967	20,081
232.85	8,967	4,448	235.50	8,967	20,261
232.90	8,967	4,822	235.55	8,967	20,440
232.95	8,967	5,195	235.60	8,967	20,619
233.00	8,967	5,567	235.65	8,967	20,799
233.05	8,967	5,937	235.70	8,967	20,978
233.10	8,967	6,306	235.75	8,967	21,157
233.15	8,967	6,673			
233.20	8,967	7,039			
233.25	8,967	7,403			
233.30	8,967	7,765			
233.35	8,967	8,125			
233.40	8,967	8,484			
233.45	8,967	8,841			
233.50	8,967	9,196			
233.55	8,967	9,549			
233.60	8,967	9,900			
233.65	8,967	10,248			
233.70	8,967	10,595			
233.75	8,967	10,939			
233.80	8,967	11,281			
233.85	8,967	11,620			
233.90	8,967	11,957			
233.95	8,967	12,291			
234.00	8,967	12,622			
234.05	8,967	12,950			
234.10	8,967	13,276			
234.15	8,967	13,598			
234.20	8,967	13,917			
234.25	8,967	14,233			
234.30	8,967	14,545			
234.35	8,967	14,854			
234.40	8,967	15,158			
234.45	8,967	15,459			
234.50	8,967	15,755			
234.55	8,967	16,047			
234.60	8,967	16,333			

Summary for Pond 2P:

Inflow Area = 16,271 sf, 0.00% Impervious, Inflow Depth = 1.34" for 10-Year event
 Inflow = 0.4 cfs @ 12.32 hrs, Volume= 1,820 cf
 Outflow = 0.0 cfs @ 14.77 hrs, Volume= 1,764 cf, Atten= 88%, Lag= 146.9 min
 Primary = 0.0 cfs @ 14.77 hrs, Volume= 1,764 cf
 Routed to Link DP-1 : WETLAND
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link DP-1 : WETLAND

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Peak Elev= 227.01' @ 14.77 hrs Surf.Area= 1,227 sf Storage= 942 cf

Plug-Flow detention time= 438.0 min calculated for 1,764 cf (97% of inflow)
 Center-of-Mass det. time= 421.1 min (1,307.6 - 886.4)

Volume	Invert	Avail.Storage	Storage Description		
#1	226.00'	2,507 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
226.00	668	110.0	0	0	668
227.00	1,221	151.0	931	931	1,529
228.00	1,960	196.0	1,576	2,507	2,784

Device	Routing	Invert	Outlet Devices
#1	Primary	226.00'	6.0" Round Culvert L= 100.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 226.00' / 225.00' S= 0.0100 ' S Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf
#2	Device 1	226.00'	1.0" Vert. Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	227.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#4	Device 1	227.50'	48.0" x 48.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#5	Secondary	227.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


Primary OutFlow Max=0.0 cfs @ 14.77 hrs HW=227.01' (Free Discharge)

- ↑ 1=Culvert (Passes 0.0 cfs of 0.6 cfs potential flow)
- ↑ 2=Orifice (Orifice Controls 0.0 cfs @ 4.74 fps)
- ↑ 3=Sharp-Crested Rectangular Weir (Weir Controls 0.0 cfs @ 0.31 fps)
- ↑ 4=Grate (Controls 0.0 cfs)

Secondary OutFlow Max=0.0 cfs @ 0.00 hrs HW=226.00' (Free Discharge)

- ↑ 5=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 2P:



Stage-Area-Storage for Pond 2P:


Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
226.00	668	0	227.06	1,260	1,005
226.02	677	13	227.08	1,274	1,030
226.04	687	27	227.10	1,287	1,056
226.06	697	41	227.12	1,300	1,082
226.08	706	55	227.14	1,314	1,108
226.10	716	69	227.16	1,328	1,135
226.12	726	84	227.18	1,341	1,161
226.14	735	98	227.20	1,355	1,188
226.16	745	113	227.22	1,369	1,215
226.18	755	128	227.24	1,382	1,243
226.20	765	143	227.26	1,396	1,271
226.22	775	159	227.28	1,410	1,299
226.24	786	174	227.30	1,424	1,327
226.26	796	190	227.32	1,439	1,356
226.28	806	206	227.34	1,453	1,385
226.30	817	222	227.36	1,467	1,414
226.32	827	239	227.38	1,481	1,443
226.34	837	255	227.40	1,496	1,473
226.36	848	272	227.42	1,510	1,503
226.38	859	289	227.44	1,525	1,534
226.40	869	307	227.46	1,539	1,564
226.42	880	324	227.48	1,554	1,595
226.44	891	342	227.50	1,569	1,626
226.46	902	360	227.52	1,584	1,658
226.48	913	378	227.54	1,598	1,690
226.50	924	396	227.56	1,613	1,722
226.52	935	415	227.58	1,628	1,754
226.54	946	434	227.60	1,644	1,787
226.56	957	453	227.62	1,659	1,820
226.58	969	472	227.64	1,674	1,853
226.60	980	491	227.66	1,689	1,887
226.62	991	511	227.68	1,705	1,921
226.64	1,003	531	227.70	1,720	1,955
226.66	1,014	551	227.72	1,736	1,990
226.68	1,026	572	227.74	1,751	2,025
226.70	1,038	592	227.76	1,767	2,060
226.72	1,049	613	227.78	1,782	2,095
226.74	1,061	634	227.80	1,798	2,131
226.76	1,073	656	227.82	1,814	2,167
226.78	1,085	677	227.84	1,830	2,204
226.80	1,097	699	227.86	1,846	2,240
226.82	1,109	721	227.88	1,862	2,277
226.84	1,121	743	227.90	1,878	2,315
226.86	1,134	766	227.92	1,894	2,353
226.88	1,146	789	227.94	1,911	2,391
226.90	1,158	812	227.96	1,927	2,429
226.92	1,171	835	227.98	1,944	2,468
226.94	1,183	859	228.00	1,960	2,507
226.96	1,196	882			
226.98	1,208	906			
227.00	1,221	931			
227.02	1,234	955			
227.04	1,247	980			

Summary for Link DP-1: WETLAND

Inflow Area = 232,202 sf, 24.54% Impervious, Inflow Depth > 1.07" for 10-Year event
Inflow = 3.1 cfs @ 12.16 hrs, Volume= 20,758 cf
Primary = 3.1 cfs @ 12.16 hrs, Volume= 20,758 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs

Link DP-1: WETLAND



250511 - POST

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 29

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PS-1A: Runoff Area=29,240 sf 3.45% Impervious Runoff Depth=3.48"
Flow Length=234' Tc=15.7 min CN=WQ Runoff=2.0 cfs 8,481 cf

Subcatchment PS-1B: Runoff Area=76,702 sf 72.98% Impervious Runoff Depth=6.56"
Tc=6.0 min CN=WQ Runoff=11.6 cfs 41,911 cf

Subcatchment PS-1C: Runoff Area=16,271 sf 0.00% Impervious Runoff Depth=3.40"
Flow Length=340' Tc=20.4 min CN=WQ Runoff=1.0 cfs 4,609 cf

Subcatchment PS-1D: Runoff Area=109,989 sf 0.00% Impervious Runoff Depth=2.92"
Flow Length=371' Tc=7.8 min CN=WQ Runoff=7.7 cfs 26,795 cf

Pond 1P: Peak Elev=234.88' Storage=17,804 cf Inflow=11.6 cfs 41,911 cf
Discarded=0.2 cfs 22,525 cf Primary=3.4 cfs 19,386 cf Outflow=3.6 cfs 41,911 cf

Pond 2P: Peak Elev=227.20' Storage=1,194 cf Inflow=1.0 cfs 4,609 cf
Primary=0.7 cfs 4,477 cf Secondary=0.0 cfs 0 cf Outflow=0.7 cfs 4,477 cf

Link DP-1: WETLAND Inflow=9.5 cfs 59,140 cf
Primary=9.5 cfs 59,140 cf

Total Runoff Area = 232,202 sf Runoff Volume = 81,796 cf Average Runoff Depth = 4.23"
75.46% Pervious = 175,212 sf 24.54% Impervious = 56,990 sf

250511 - POST

Prepared by R Levesque Associates
 HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=7.96"

Printed 9/30/2025

Page 30

Summary for Subcatchment PS-1A:

Runoff = 2.0 cfs @ 12.22 hrs, Volume= 8,481 cf, Depth= 3.48"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
16,864	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
8,399	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
29,240		Weighted Average
28,231	60	96.55% Pervious Area
1,009	98	3.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.7	100	0.0800	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.00"
3.0	134	0.0224	0.75		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.7	234	Total			

Subcatchment PS-1A:

Hydrograph



Summary for Subcatchment PS-1B:


Runoff = 11.6 cfs @ 12.09 hrs, Volume= 41,911 cf, Depth= 6.56"
 Routed to Pond 1P :

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
20,722	61	>75% Grass cover, Good, HSG B
27,201	98	Paved parking, HSG B
28,779	98	Roofs, HSG B
76,702		Weighted Average
20,722	61	27.02% Pervious Area
55,980	98	72.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PS-1B:



Summary for Subcatchment PS-1C:

Runoff = 1.0 cfs @ 12.30 hrs, Volume= 4,609 cf, Depth= 3.40"
 Routed to Pond 2P :


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
15,907	61	>75% Grass cover, Good, HSG B
364	55	Woods, Good, HSG B
16,271		Weighted Average
16,271	61	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
19.2	100	0.0300	0.09		Sheet Flow, Grass: Bermuda n= 0.410 P2= 3.00"
1.2	240	0.0458	3.45		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
20.4	340	Total			

Subcatchment PS-1C:

Hydrograph



Summary for Subcatchment PS-1D:

Runoff = 7.7 cfs @ 12.12 hrs, Volume= 26,795 cf, Depth= 2.92"
 Routed to Link DP-1 : WETLAND


Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
27,867	61	>75% Grass cover, Good, HSG B
0	98	Roofs, HSG B
82,121	55	Woods, Good, HSG B
109,989		Weighted Average
109,989	57	100.00% Pervious Area
0	98	0.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.3	100	0.0650	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.00"
1.5	271	0.0424	3.09		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
7.8	371	Total			

Subcatchment PS-1D:

Hydrograph



Summary for Pond 1P:

Inflow Area = 76,702 sf, 72.98% Impervious, Inflow Depth = 6.56" for 100-Year event
 Inflow = 11.6 cfs @ 12.09 hrs, Volume= 41,911 cf
 Outflow = 3.6 cfs @ 12.41 hrs, Volume= 41,911 cf, Atten= 69%, Lag= 19.5 min
 Discarded = 0.2 cfs @ 7.40 hrs, Volume= 22,525 cf
 Primary = 3.4 cfs @ 12.41 hrs, Volume= 19,386 cf
 Routed to Link DP-1 : WETLAND

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Peak Elev= 234.88' @ 12.41 hrs Surf.Area= 8,967 sf Storage= 17,804 cf

Plug-Flow detention time= 285.9 min calculated for 41,911 cf (100% of inflow)
 Center-of-Mass det. time= 285.9 min (1,041.6 - 755.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	232.00'	8,312 cf	68.00'W x 131.87'L x 3.75'H Field A 33,626 cf Overall - 12,845 cf Embedded = 20,781 cf x 40.0% Voids
#2A	232.50'	12,845 cf	ADS_StormTech SC-800 +Cap x 252 Inside #1 Effective Size= 45.0"W x 33.0"H => 7.11 sf x 7.12'L = 50.6 cf Overall Size= 51.0"W x 33.0"H x 7.55'L with 0.43' Overlap 252 Chambers in 14 Rows Cap Storage= 3.4 cf x 2 x 14 rows = 95.8 cf
		21,157 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	231.00'	12.0" Round Culvert L= 192.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 231.00' / 227.00' S= 0.0208 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	234.50'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Device 1	233.00'	3.0" W x 3.0" H Vert. Orifice C= 0.600 Limited to weir flow at low heads
#4	Discarded	232.00'	1.020 in/hr Exfiltration over Surface area Phase-In= 0.01'

Discarded OutFlow Max=0.2 cfs @ 7.40 hrs HW=232.04' (Free Discharge)

↳ **4=Exfiltration** (Exfiltration Controls 0.2 cfs)

Primary OutFlow Max=3.3 cfs @ 12.41 hrs HW=234.87' (Free Discharge)

↳ **1=Culvert** (Passes 3.3 cfs of 6.1 cfs potential flow)

↳ **2=Sharp-Crested Rectangular Weir** (Weir Controls 2.9 cfs @ 2.00 fps)

↳ **3=Orifice** (Orifice Controls 0.4 cfs @ 6.37 fps)

Pond 1P: - Chamber Wizard Field A

Chamber Model = ADS_StormTech SC-800 +Cap (ADS StormTech® SC-800 with cap volume)

Effective Size= 45.0"W x 33.0"H => 7.11 sf x 7.12'L = 50.6 cf

Overall Size= 51.0"W x 33.0"H x 7.55'L with 0.43' Overlap

Cap Storage= 3.4 cf x 2 x 14 rows = 95.8 cf

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

18 Chambers/Row x 7.12' Long +0.88' Cap Length x 2 = 129.87' Row Length +12.0" End Stone x 2 = 131.87' Base Length

14 Rows x 51.0" Wide + 6.0" Spacing x 13 + 12.0" Side Stone x 2 = 68.00' Base Width

6.0" Stone Base + 33.0" Chamber Height + 6.0" Stone Cover = 3.75' Field Height

252 Chambers x 50.6 cf + 3.4 cf Cap Volume x 2 x 14 Rows = 12,845.0 cf Chamber Storage

33,626.0 cf Field - 12,845.0 cf Chambers = 20,781.0 cf Stone x 40.0% Voids = 8,312.4 cf Stone Storage

Chamber Storage + Stone Storage = 21,157.4 cf = 0.486 af


Overall Storage Efficiency = 62.9%

Overall System Size = 131.87' x 68.00' x 3.75'


252 Chambers

1,245.4 cy Field

769.7 cy Stone



Pond 1P:



Stage-Area-Storage for Pond 1P:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
232.00	8,967	0	234.65	8,967	16,615
232.05	8,967	179	234.70	8,967	16,891
232.10	8,967	359	234.75	8,967	17,160
232.15	8,967	538	234.80	8,967	17,423
232.20	8,967	717	234.85	8,967	17,678
232.25	8,967	897	234.90	8,967	17,923
232.30	8,967	1,076	234.95	8,967	18,157
232.35	8,967	1,255	235.00	8,967	18,379
232.40	8,967	1,435	235.05	8,967	18,590
232.45	8,967	1,614	235.10	8,967	18,793
232.50	8,967	1,793	235.15	8,967	18,990
232.55	8,967	2,176	235.20	8,967	19,180
232.60	8,967	2,557	235.25	8,967	19,364
232.65	8,967	2,938	235.30	8,967	19,543
232.70	8,967	3,317	235.35	8,967	19,723
232.75	8,967	3,695	235.40	8,967	19,902
232.80	8,967	4,072	235.45	8,967	20,081
232.85	8,967	4,448	235.50	8,967	20,261
232.90	8,967	4,822	235.55	8,967	20,440
232.95	8,967	5,195	235.60	8,967	20,619
233.00	8,967	5,567	235.65	8,967	20,799
233.05	8,967	5,937	235.70	8,967	20,978
233.10	8,967	6,306	235.75	8,967	21,157
233.15	8,967	6,673			
233.20	8,967	7,039			
233.25	8,967	7,403			
233.30	8,967	7,765			
233.35	8,967	8,125			
233.40	8,967	8,484			
233.45	8,967	8,841			
233.50	8,967	9,196			
233.55	8,967	9,549			
233.60	8,967	9,900			
233.65	8,967	10,248			
233.70	8,967	10,595			
233.75	8,967	10,939			
233.80	8,967	11,281			
233.85	8,967	11,620			
233.90	8,967	11,957			
233.95	8,967	12,291			
234.00	8,967	12,622			
234.05	8,967	12,950			
234.10	8,967	13,276			
234.15	8,967	13,598			
234.20	8,967	13,917			
234.25	8,967	14,233			
234.30	8,967	14,545			
234.35	8,967	14,854			
234.40	8,967	15,158			
234.45	8,967	15,459			
234.50	8,967	15,755			
234.55	8,967	16,047			
234.60	8,967	16,333			

Summary for Pond 2P:

Inflow Area = 16,271 sf, 0.00% Impervious, Inflow Depth = 3.40" for 100-Year event
 Inflow = 1.0 cfs @ 12.30 hrs, Volume= 4,609 cf
 Outflow = 0.7 cfs @ 12.52 hrs, Volume= 4,477 cf, Atten= 30%, Lag= 13.8 min
 Primary = 0.7 cfs @ 12.52 hrs, Volume= 4,477 cf
 Routed to Link DP-1 : WETLAND
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link DP-1 : WETLAND

Routing by Stor-Ind method, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
 Peak Elev= 227.20' @ 12.52 hrs Surf.Area= 1,358 sf Storage= 1,194 cf

Plug-Flow detention time= 208.5 min calculated for 4,477 cf (97% of inflow)
 Center-of-Mass det. time= 192.3 min (1,050.2 - 857.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	226.00'	2,507 cf	Custom Stage Data (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
226.00	668	110.0	0	0	668	
227.00	1,221	151.0	931	931	1,529	
228.00	1,960	196.0	1,576	2,507	2,784	

Device	Routing	Invert	Outlet Devices
#1	Primary	226.00'	6.0" Round Culvert L= 100.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 226.00' / 225.00' S= 0.0100 ' /' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.20 sf
#2	Device 1	226.00'	1.0" Vert. Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	227.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#4	Device 1	227.50'	48.0" x 48.0" Horiz. Gate C= 0.600 Limited to weir flow at low heads
#5	Secondary	227.50'	10.0' long x 10.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


Primary OutFlow Max=0.7 cfs @ 12.52 hrs HW=227.20' (Free Discharge)

- ↑ 1=Culvert (Barrel Controls 0.7 cfs @ 3.47 fps)
- ↑ 2=Orifice (Passes < 0.0 cfs potential flow)
- ↑ 3=Sharp-Crested Rectangular Weir (Passes < 1.2 cfs potential flow)
- ↑ 4=Gate (Controls 0.0 cfs)

Secondary OutFlow Max=0.0 cfs @ 0.00 hrs HW=226.00' (Free Discharge)

- ↑ 5=Broad-Crested Rectangular Weir (Controls 0.0 cfs)

Pond 2P:



Stage-Area-Storage for Pond 2P:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
226.00	668	0	227.06	1,260	1,005
226.02	677	13	227.08	1,274	1,030
226.04	687	27	227.10	1,287	1,056
226.06	697	41	227.12	1,300	1,082
226.08	706	55	227.14	1,314	1,108
226.10	716	69	227.16	1,328	1,135
226.12	726	84	227.18	1,341	1,161
226.14	735	98	227.20	1,355	1,188
226.16	745	113	227.22	1,369	1,215
226.18	755	128	227.24	1,382	1,243
226.20	765	143	227.26	1,396	1,271
226.22	775	159	227.28	1,410	1,299
226.24	786	174	227.30	1,424	1,327
226.26	796	190	227.32	1,439	1,356
226.28	806	206	227.34	1,453	1,385
226.30	817	222	227.36	1,467	1,414
226.32	827	239	227.38	1,481	1,443
226.34	837	255	227.40	1,496	1,473
226.36	848	272	227.42	1,510	1,503
226.38	859	289	227.44	1,525	1,534
226.40	869	307	227.46	1,539	1,564
226.42	880	324	227.48	1,554	1,595
226.44	891	342	227.50	1,569	1,626
226.46	902	360	227.52	1,584	1,658
226.48	913	378	227.54	1,598	1,690
226.50	924	396	227.56	1,613	1,722
226.52	935	415	227.58	1,628	1,754
226.54	946	434	227.60	1,644	1,787
226.56	957	453	227.62	1,659	1,820
226.58	969	472	227.64	1,674	1,853
226.60	980	491	227.66	1,689	1,887
226.62	991	511	227.68	1,705	1,921
226.64	1,003	531	227.70	1,720	1,955
226.66	1,014	551	227.72	1,736	1,990
226.68	1,026	572	227.74	1,751	2,025
226.70	1,038	592	227.76	1,767	2,060
226.72	1,049	613	227.78	1,782	2,095
226.74	1,061	634	227.80	1,798	2,131
226.76	1,073	656	227.82	1,814	2,167
226.78	1,085	677	227.84	1,830	2,204
226.80	1,097	699	227.86	1,846	2,240
226.82	1,109	721	227.88	1,862	2,277
226.84	1,121	743	227.90	1,878	2,315
226.86	1,134	766	227.92	1,894	2,353
226.88	1,146	789	227.94	1,911	2,391
226.90	1,158	812	227.96	1,927	2,429
226.92	1,171	835	227.98	1,944	2,468
226.94	1,183	859	228.00	1,960	2,507
226.96	1,196	882			
226.98	1,208	906			
227.00	1,221	931			
227.02	1,234	955			
227.04	1,247	980			


Summary for Link DP-1: WETLAND

Inflow Area = 232,202 sf, 24.54% Impervious, Inflow Depth > 3.06" for 100-Year event
Inflow = 9.5 cfs @ 12.13 hrs, Volume= 59,140 cf
Primary = 9.5 cfs @ 12.13 hrs, Volume= 59,140 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs


Link DP-1: WETLAND

Hydrograph



Appendix D: Hydraulic Analysis

Hydraflow Storm Sewers Extension for Autodesk® Civil 3D® Plan



Storm Sewer Tabulation

Station		Len (ft)	Drng Area		Rnoff coeff (C)	Area x C		Tc		Rain (l) (in/hr)	Total flow (cfs)	Cap full (cfs)	Vel (ft/s)	Pipe		Invert Elev		HGL Elev		Grnd / Rim Elev		Line ID
Line	To Line		Incr (ac)	Total (ac)		Incr	Total	Inlet (min)	Syst (min)					Size (in)	Slope (%)	Dn (ft)	Up (ft)	Dn (ft)	Up (ft)	Dn (ft)	Up (ft)	
1	End	22.795	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	2.20	1.21	6.32	8	1.01	234.00	234.23	234.65	235.37	240.24	236.87	P-D-PIPE-(58)
2	End	34.983	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	2.20	1.21	6.32	8	1.00	234.50	234.85	235.15	236.26	236.05	236.50	P-D-PIPE-(64)
3	End	34.405	0.00	0.00	0.00	0.00	0.00	0.0	0.1	0.0	4.20	5.04	5.67	12	2.00	233.94	234.63	234.87	235.49	238.90	237.70	P-D-PIPE-(20)
4	3	13.604	0.00	0.00	0.00	0.00	0.00	0.0	0.1	0.0	3.00	5.02	4.74	12	1.98	234.73	235.00	235.49	235.74	237.70	237.60	P-D-PIPE-(19)
5	4	9.235	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	0.70	1.19	3.40	8	0.97	236.00	236.09	236.37	236.48	237.60	237.64	P-D-PIPE-(66)
6	End	25.239	0.00	0.00	0.00	0.00	0.00	0.0	0.1	0.0	3.10	5.05	4.57	12	2.01	235.12	235.63	236.00	236.38	239.88	239.57	P-D-PIPE-(3)
7	6	13.598	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	1.30	5.02	2.94	12	1.99	235.73	236.00	236.38	236.48	239.57	239.75	P-D-PIPE-(6)
8	6	13.598	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	1.80	5.02	3.60	12	1.99	235.73	236.00	236.38	236.57	239.57	239.51	P-D-PIPE-(2)
9	3	13.605	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	1.20	5.02	2.63	12	1.98	234.73	235.00	235.49	235.46	237.70	237.45	P-D-PIPE-(18)
10	End	160.594	0.00	0.00	0.00	0.00	0.00	0.0	0.0	0.0	2.60	2.81	3.95	12	0.62	232.00	233.00	232.85	233.73	233.19	236.00	P-D-PIPE-(1)

Project File: cadexport.stm

Number of lines: 10

Run Date: 9/30/2025

NOTES: Known Qs only ; c = cir e = ellip b = box

PYD-1

PCB-1

PCB-2

PRD-1

PCB-4

PCB-3

PRD-3

PRD-5

Subcat

Reach

Pond

Link

Routing Diagram for 250511 - INLET
Prepared by R Levesque Associates, Printed 9/30/2025
HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

250511 - INLET

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 2

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	100-Year	Type III 24-hr		Default	24.00	1	7.96	2

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 3

Time span=0.00-36.00 hrs, dt=0.05 hrs, 721 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-Q
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PCB-1:	Runoff Area=8,568 sf 70.91% Impervious Runoff Depth=6.47" Tc=6.0 min CN=WQ Runoff=1.3 cfs 4,618 cf
Subcatchment PCB-2:	Runoff Area=13,212 sf 52.76% Impervious Runoff Depth=5.69" Tc=6.0 min CN=WQ Runoff=1.8 cfs 6,260 cf
Subcatchment PCB-3:	Runoff Area=8,947 sf 47.61% Impervious Runoff Depth=5.46" Tc=6.0 min CN=WQ Runoff=1.2 cfs 4,074 cf
Subcatchment PCB-4:	Runoff Area=16,257 sf 57.68% Impervious Runoff Depth=5.90" Tc=6.0 min CN=WQ Runoff=2.3 cfs 7,990 cf
Subcatchment PRD-1:	Runoff Area=12,489 sf 100.00% Impervious Runoff Depth=7.72" Tc=6.0 min CN=98 Runoff=2.2 cfs 8,035 cf
Subcatchment PRD-3:	Runoff Area=12,489 sf 100.00% Impervious Runoff Depth=7.72" Tc=6.0 min CN=98 Runoff=2.2 cfs 8,035 cf
Subcatchment PRD-5:	Runoff Area=4,163 sf 100.00% Impervious Runoff Depth=7.72" Tc=6.0 min CN=98 Runoff=0.7 cfs 2,678 cf
Subcatchment PYD-1:	Runoff Area=29,240 sf 3.45% Impervious Runoff Depth=3.48" Tc=6.0 min CN=WQ Runoff=2.6 cfs 8,481 cf

Total Runoff Area = 105,364 sf Runoff Volume = 50,171 cf Average Runoff Depth = 5.71"
46.06% Pervious = 48,533 sf 53.94% Impervious = 56,831 sf

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 4

Summary for Subcatchment PCB-1:

Runoff = 1.3 cfs @ 12.09 hrs, Volume= 4,618 cf, Depth= 6.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
2,493	61	>75% Grass cover, Good, HSG B
6,076	98	Paved parking, HSG B
8,568		Weighted Average
2,493	61	29.09% Pervious Area
6,076	98	70.91% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 5

Summary for Subcatchment PCB-2:

Runoff = 1.8 cfs @ 12.09 hrs, Volume= 6,260 cf, Depth= 5.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
6,242	61	>75% Grass cover, Good, HSG B
6,970	98	Paved parking, HSG B
13,212		Weighted Average
6,242	61	47.24% Pervious Area
6,970	98	52.76% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment PCB-3:

Runoff = 1.2 cfs @ 12.09 hrs, Volume= 4,074 cf, Depth= 5.46"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
4,688	61	>75% Grass cover, Good, HSG B
4,259	98	Paved parking, HSG B
8,947		Weighted Average
4,688	61	52.39% Pervious Area
4,259	98	47.61% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment PCB-4:

Runoff = 2.3 cfs @ 12.09 hrs, Volume= 7,990 cf, Depth= 5.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
6,880	61	>75% Grass cover, Good, HSG B
9,377	98	Paved parking, HSG B
16,257		Weighted Average
6,880	61	42.32% Pervious Area
9,377	98	57.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 8

Summary for Subcatchment PRD-1:

Runoff = 2.2 cfs @ 12.09 hrs, Volume= 8,035 cf, Depth= 7.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
12,489	98	Roofs, HSG B
12,489	98	100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 9

Summary for Subcatchment PRD-3:

Runoff = 2.2 cfs @ 12.09 hrs, Volume= 8,035 cf, Depth= 7.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
12,489	98	Roofs, HSG B
12,489	98	100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 10

Summary for Subcatchment PRD-5:

Runoff = 0.7 cfs @ 12.09 hrs, Volume= 2,678 cf, Depth= 7.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
4,163	98	Roofs, HSG B
4,163	98	100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

250511 - INLET

Type III 24-hr 100-Year Rainfall=7.96"

Prepared by R Levesque Associates

Printed 9/30/2025

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Page 11

Summary for Subcatchment PYD-1:

Runoff = 2.6 cfs @ 12.10 hrs, Volume= 8,481 cf, Depth= 3.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-Q, Time Span= 0.00-36.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-Year Rainfall=7.96"

Area (sf)	CN	Description
16,863	61	>75% Grass cover, Good, HSG B
234	74	>75% Grass cover, Good, HSG C
1,009	98	Roofs, HSG B
8,399	55	Woods, Good, HSG B
2,734	70	Woods, Good, HSG C
29,240		Weighted Average
28,231	60	96.55% Pervious Area
1,009	98	3.45% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Appendix E: MassDEP Calculations

- Impervious Area Calculations
- Recharge Calculation
- Stage Storage Chart – Subsurface Infiltration Basin
- Water Quality Flow Rate Calculations – PWQU-1
- Water Quality Flow Rate Calculations – PWQU-2
- Water Quality Conversion Table
- TSS Removal Worksheet – Subsurface Infiltration Basin
- Drawdown Calculation
- Barracuda Max Info Sheet
- NJDEP Barracuda Max Certification
- Barracuda Max Maintenance Guide

Standard 3: Recharge Calculations

Impervious Area Calculations

Existing Total Impervious Area

Sub-Catchment	Roof (sf)	Other Impervious (sf)	Sum (sf)
ES-1	1,009	0	1,009
	1,009	0	1,009

Proposed Total Impervious Area

Sub-Catchment	Roof (sf)	Other Impervious (sf)	Sum (sf)	
PS-1A	1,009	0	1,009	
PS-1B	28,779	27,201	55,980	Tributary to Basin
PS-1C	0	0	0	
PS-1D	0	0	0	
	29,788	27,201	56,989	

Total Existing Impervious Area	1,009 SF
Total Proposed Impervious Area	56,989 SF
Total New Impervious Area	55,980 SF
Total Impervious Area Tributary to Infiltration Basin	55,980 SF

Standard 3: Recharge Calculations -Subsurface Infiltration Basin

$$R_v \text{ (required)} = F \times \text{Impervious Area}$$

where: R_v = Required Recharge Volume (cu. ft.)

F = Target Depth Factor	0.60 inch (A-soils)
	0.35 inch (B-soils)
	0.25 inch (C-soils)
	0.10 inch (D-soils)

New Impervious Area by Hydrologic Soil Type

Impervious Area (A-soils)	0 sq. ft.	0.0%
Impervious Area (B-soils)	55,980 sq. ft.	100.0%
Impervious Area (C-soils)	0 sq. ft.	0.0%
Impervious Area (D-soils)	0 sq. ft.	0.0%
Total Impervious area	55,980 sq. ft.	100.0%

Required Recharge Volume Sizing (R_v)

$$R_v \text{ (required)} = \sum [F_{\text{Soil Type}} \times \text{Impervious Area}_{\text{Soil Type}}] \times 1 \text{ ft./12 in.}$$

$$R_v \text{ (required)} = 1,633 \text{ cu. ft.}$$

$$R_v \text{ (provided)} = 5,567 \text{ cu. ft.*} \quad (\text{Subsurface Infiltration Basin})$$

*Volume represents the available storage in subsurface infiltration basin below orifice elevation 233.00 ft

250511 - POST

Prepared by R Levesque Associates

HydroCAD® 10.20-7a s/n 13073 © 2025 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=7.96"

Printed 9/30/2025

Stage-Area-Storage for Pond 1P:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
232.00	8,967	0	234.65	8,967	16,615
232.05	8,967	179	234.70	8,967	16,891
232.10	8,967	359	234.75	8,967	17,160
232.15	8,967	538	234.80	8,967	17,423
232.20	8,967	717	234.85	8,967	17,678
232.25	8,967	897	234.90	8,967	17,923
232.30	8,967	1,076	234.95	8,967	18,157
232.35	8,967	1,255	235.00	8,967	18,379
232.40	8,967	1,435	235.05	8,967	18,590
232.45	8,967	1,614	235.10	8,967	18,793
232.50	8,967	1,793	235.15	8,967	18,990
232.55	8,967	2,176	235.20	8,967	19,180
232.60	8,967	2,557	235.25	8,967	19,364
232.65	8,967	2,938	235.30	8,967	19,543
232.70	8,967	3,317	235.35	8,967	19,723
232.75	8,967	3,695	235.40	8,967	19,902
232.80	8,967	4,072	235.45	8,967	20,081
232.85	8,967	4,448	235.50	8,967	20,261
232.90	8,967	4,822	235.55	8,967	20,440
232.95	8,967	5,195	235.60	8,967	20,619
233.00	8,967	5,567	235.65	8,967	20,799
233.05	8,967	5,937	235.70	8,967	20,978
233.10	8,967	6,306	235.75	8,967	21,157
233.15	8,967	6,673			
233.20	8,967	7,039			
233.25	8,967	7,403			
233.30	8,967	7,765			
233.35	8,967	8,125			
233.40	8,967	8,484			
233.45	8,967	8,841			
233.50	8,967	9,196			
233.55	8,967	9,549			
233.60	8,967	9,900			
233.65	8,967	10,248			
233.70	8,967	10,595			
233.75	8,967	10,939			
233.80	8,967	11,281			
233.85	8,967	11,620			
233.90	8,967	11,957			
233.95	8,967	12,291			
234.00	8,967	12,622			
234.05	8,967	12,950			
234.10	8,967	13,276			
234.15	8,967	13,598			
234.20	8,967	13,917			
234.25	8,967	14,233			
234.30	8,967	14,545			
234.35	8,967	14,854			
234.40	8,967	15,158			
234.45	8,967	15,459			
234.50	8,967	15,755			
234.55	8,967	16,047			
234.60	8,967	16,333			

Standard 4: Water Quality - PWQU-1

Water Quality Volume Conversion to Flow Rate

Note: Required water quality volume 0.5-inch of runoff

$$Q = (qu) (A) (WQV)$$

where: **Q** = peak flow rate associated with first 0.5-inch of runoff (c.f.s.)

qu = unit peak discharge (csm/in) - value taken from table based on t_c

A = impervious surface drainage area (sq. mi.)

WQV = water quality volume in watershed inches

· Proposed Water Quality Unit (PWQU-1)

t_c =	0.100 hrs	
qu =	752 csm/in	(from table)
A =	0.00047 sq. mi.*	
WQV =	0.5 inch	

$$Q_{0.5} = \quad \quad \quad 0.18 \text{ c.f.s}$$

The Baracuda Max Model S4 provides 80% TSS treatment of flows up to 1.52 c.f.s.

* Only includes impervious area tributary to water quality unit

Standard 4: Water Quality - PWQU-2

Water Quality Volume Conversion to Flow Rate

Note: Required water quality volume 0.5-inch of runoff

$$Q = (qu) (A) (WQV)$$

where: **Q** = peak flow rate associated with first 0.5-inch of runoff (c.f.s.)

qu = unit peak discharge (csm/in) - value taken from table based on t_c

A = impervious surface drainage area (sq. mi.)

WQV = water quality volume in watershed inches

· Proposed Water Quality Unit (PWQU-2)

t_c =	0.100 hrs	
qu =	752 csm/in	(from table)
A =	0.00047 sq. mi.*	
WQV =	0.5 inch	

$$Q_{0.5} = 0.18 \text{ c.f.s}$$

The Baracuda Max Model S4 provides 80% TSS treatment of flows up to 1.52 c.f.s.

* Only includes impervious area tributary to water quality unit

Figure 2: For First ½-inch of Runoff, Table of qu values for Ia/P Curve = 0.0.058, listed by tc, for Type III Storm Distribution

Tc (Hours)	qu (csm/in)	Tc (Hours)	qu (csm/in)	Tc (Hours)	qu (csm/in)	Tc (Hours)	qu (csm/in)
0.01	821	1.8	246	5.3	116	8.8	77
0.03	821	1.9	238	5.4	115	8.9	76
0.05	813	2	230	5.5	113	9	76
0.067	794	2.1	223	5.6	112	9.1	75
0.083	773	2.2	217	5.7	110	9.2	74
0.1	752	2.3	211	5.8	109	9.3	74
0.116	733	2.4	205	5.9	107	9.4	73
0.133	713	2.5	200	6	106	9.5	72
0.15	694	2.6	194	6.1	104	9.6	72
0.167	677	2.7	190	6.2	103	9.7	71
0.183	662	2.8	185	6.3	102	9.8	70
0.2	646	2.9	181	6.4	100	9.9	70
0.217	632	3	176	6.5	99	10	69
0.233	619	3.1	173	6.6	98		
0.25	606	3.2	169	6.7	97		
0.3	572	3.3	165	6.8	96		
0.333	552	3.4	162	6.9	94		
0.35	542	3.5	158	7	93		
0.4	516	3.6	155	7.1	92		
0.416	508	3.7	152	7.2	91		
0.5	472	3.8	149	7.3	90		
0.583	443	3.9	147	7.4	89		
0.6	437	4	144	7.5	88		
0.667	417	4.1	141	7.6	87		
0.7	408	4.2	139	7.7	86		
0.8	383	4.3	136	7.8	85		
0.9	361	4.4	134	7.9	84		
1	342	4.5	132	8	84		
1.1	325	4.6	130	8.1	83		
1.2	311	4.7	128	8.2	82		
1.3	297	4.8	126	8.3	81		
1.4	285	4.9	124	8.4	80		
1.5	274	5	122	8.5	79		
1.6	264	5.1	120	8.6	79		
1.7	254	5.2	118	8.7	78		

TSS Removal Form - Infiltration Basin

Pre-Treatment	BMP	TSS Removal Rate	Starting TSS Load	Amount Removed	Remaining Load
	Deep Sump Hooded Catch Basin	0.25	1.00	0.25	0.75
	Proprietary Sedimentation Device	0.50	0.75	0.38	0.38

Pre-Treatment TSS Removal = **63%**

Total TSS Removal	BMP	TSS Removal Rate	Starting TSS Load	Amount Removed	Remaining Load
	Subsurface Infiltration	0.8	1.00	0.8	0.20

Total TSS Removal = **80%**

Drawdown Analysis

$$T_{\text{DRAWDOWN}} = \frac{R_v}{KA}$$

where: T_{DRAWDOWN} = time in hours

R_v = required recharge volume (cu. ft.)

K = Rawls rate **8.27 inches/hour (A-soils)***

1.02 inches/hour (B-soils)*

0.27 inches/hour (C-soils)*

A = bottom area of recharge facility (sq. ft.)

Subsurface Infiltration Basin

R_v = 1,633 cu. ft.

A = 8,967 sq. ft.

$T_{\text{DRAWDOWN}} =$ **2.1 hours < 72 hours (B-soils)**

Barracuda[®] Max


The Barracuda Max is market-changing stormwater quality technology. This high-performance vortex hydrodynamic separator is designed to remove total suspended solids in order to protect our precious receiving waters. The Barracuda Max is also an outstanding value that offers multiple pipe configurations, and quick installation. The “Max” version of the Barracuda is built on the base platform of the original ADS Barracuda with improved removal efficiencies and installation components.

Features

- Single manhole design
- No elevation loss between the inlet and outlet
- Variable inlet/outlet angle configurations (not just 180 degree orientation)
- Internal bypass for inline installation (where applicable)
- Revolutionary, patent pending “teeth” mitigate turbulence in the sump area to prevent resuspension of captured contaminants
- Available with grated drop inlet configuration
- Available with trash and/or oil capture add-ons

Benefits

- Internal components are in stock for quick delivery
- The S3, S4, S6, and S8 can be installed in a standard 36” (900 mm), 48” (1200 mm), 72” (1800 mm), and 96” (2400 mm) precast manhole, respectively
- The S3 & S4 can be provided factory installed within a 36” (900 mm) and 48” (1200 mm) ADS HP manhole and delivered to the jobsite
- The Barracuda Max “teeth” and deflector plate apparatus are fabricated and designed for quick and easy field assembly
- Designed for easy maintenance using a vacuum truck or similar equipment.
- Inspection and maintenance are performed from the surface with no confined space entry



Barrucuda Specification

Materials and Design

- Concrete Structures: Designed for H-20 traffic loading and applicable soil loads or as otherwise determined by a Licensed Professional Engineer. The materials and structural design of the devices shall be per ASTM C857 and ASTM C858.
- 36" (900 mm) and 48" (1200 mm) HP Manhole Structures: Made from an impact modified copolymer polypropylene meeting the material requirements of ASTM F2764. The eccentric cone reducer shall be manufactured from polyethylene material meeting ASTM D3350 cell class 213320C. Gaskets shall be made of material meeting the requirements of ASTM F477.
- Separator internals shall be substantially constructed of stainless steel, polyethylene or other thermoplastic material approved by the manufacturer.

Performance

- The stormwater treatment unit shall be an inline unit capable of conveying 100% of the design peak flow. If peak flow rates exceed maximum hydraulic rate, the unit shall be installed offline.
- The Barracuda Max unit shall be designed to remove at least 80% of the suspended solids on an annual aggregate removal basis. Said removal shall be based on full-scale third party testing using OK-110 media gradation or equivalent and 300 mg/L influent concentration. Said full scale testing shall have included sediment capture based on actual total mass collected by the stormwater treatment unit.

- OR -

The Barracuda Max unit shall be designed to remove at least 50% of TSS using a media mix with d_{50} =75 micron and 200 mg/L influent concentration.

- OR -

The Barracuda Max unit shall be designed to remove at least 50% of TSS per current NJDEP/NJCAT HDS protocol.

- The stormwater treatment unit internals shall consist of (1) separator cone assembly, and (1) sump assembly, which includes the "teeth".

Barracuda Max Model	Manhole Diameter	OK-110 (80% removal)	Pretreatment for Infiltration ¹
S3	36" (900 mm)	0.86 CFS (24.1 L/s)	1.65 CFS (46.7 L/s)
S4	48" (1200 mm)	1.52 CFS (43.0 L/s)	2.94 CFS (83.3 L/s)
S6	72" (1800 mm)	3.42 CFS (96.8 L/s)	6.62 CFS (187.5 L/s)
S8	96" (2400 mm)	6.08 CFS (172.2 L/s)	11.76 CFS (333.0 L/s)

* Peak bypass flows are dependent on final design

¹ 50% removal of OK-110.

Installation

Installation of the stormwater treatment unit(s) shall be performed per manufacturer's installation instructions. Such instructions can be obtained by calling Advanced Drainage Systems at 800-821-6710 or by logging on to www.adspipe.com.





State of New Jersey

DEPARTMENT OF ENVIRONMENTAL PROTECTION
Bureau of NJPDES Stormwater Permitting & Water
Quality Management
Division of Watershed Protection and Restoration
401-02B
Post Office Box 420
Trenton, New Jersey 08625-0420
609-633-7021 Fax: 609-777-0432

PHILIP D. MURPHY
Governor

SHEILA Y. OLIVER
Lt. Governor

SHAWN M. LATOURETTE
Acting Commissioner

April 28, 2021

Daniel J. Figola, P.E.
Director of Sustainability Development
Advanced Drainage Systems, Inc.
1030 Deer Hollow Drive
Mt. Airy, MD 21771

Re: MTD Lab Certification
Barracuda™ MAX Hydrodynamic Separator Stormwater Treatment Device
On-line Installation

TSS Removal Rate 50%

Dear Mr. Figola:

The Stormwater Management rules under N.J.A.C. 7:8-5.5(b) and 5.7(c) allow the use of manufactured treatment devices (MTDs) for compliance with the design and performance standards at N.J.A.C. 7:8-5 if the pollutant removal rates have been verified by the New Jersey Corporation for Advanced Technology (NJCAT) and have been certified by the New Jersey Department of Environmental Protection (NJDEP). Advanced Drainage Systems, Inc. (ADS) has requested an MTD Laboratory Certification for the Barracuda™ MAX Hydrodynamic Separator stormwater treatment system (Barracuda™ MAX).

The project falls under the “Procedure for Obtaining Verification of a Stormwater Manufactured Treatment Device from New Jersey Corporation for Advance Technology” dated January 25, 2013. The applicable protocol is the “New Jersey Laboratory Testing Protocol to Assess Total Suspended Solids Removal by a Hydrodynamic Sedimentation Manufactured Treatment Device” dated January 25, 2013.

NJCAT verification documents submitted to the NJDEP indicate that the requirements of the aforementioned protocol have been met or exceeded. The NJCAT letter also included a recommended certification TSS removal rate and the required maintenance plan. The NJCAT Verification Report with the Verification Appendix (dated April 2021) for this device is published online at <http://www.njcat.org/verification-process/technology-verification-database.html>.

The NJDEP certifies the use of the Barracuda™ MAX stormwater treatment system at a TSS removal rate of 50% when designed, operated, and maintained in accordance with the information provided in the Verification Appendix and the following conditions:

1. The maximum treatment flow rate (MTFR) for the manufactured treatment device (MTD) is calculated using the New Jersey Water Quality Design Storm (1.25 inches in 2 hrs) in N.J.A.C. 7:8-5.5.
2. The Barracuda™ MAX shall be installed using the same configuration reviewed by NJCAT and shall be sized in accordance with the criteria specified in item 6 below.
3. This Barracuda™ MAX cannot be used in series with another MTD or a media filter (such as a sand filter) to achieve an enhanced removal rate for total suspended solids (TSS) removal under N.J.A.C. 7:8-5.5.
4. Additional design criteria for MTDs can be found in Chapter 11.3 of the New Jersey Stormwater Best Management Practices (NJ Stormwater BMP) Manual, which can be found online at www.njstormwater.org.
5. The maintenance plan for a site using this device shall incorporate, at a minimum, the maintenance requirements for the Barracuda™ MAX. A copy of the maintenance plan is attached to this certification. However, it is recommended to review the maintenance website at <https://assets.ads-pipe.com/m/2c834056a5a22888/original/Barracuda-Maintenance-Guide-MG1-01.pdf> for any changes to the maintenance requirements.
6. Sizing Requirement:

The example on the following page demonstrates the sizing procedure for the Barracuda™ MAX:

Example: A 0.25-acre impervious site is to be treated to 50% TSS removal using an Barracuda™ MAX treatment unit. The impervious site runoff (Q) based on the New Jersey Water Quality Design Storm was determined to be 0.79 cfs.

Maximum Treatment Flow Rate (MTFR) Evaluation:

The site runoff (Q) was based on the following:
 time of concentration = 10 minutes
 $i = 3.2$ in/hr (page 74, Fig. 5-16 of the NJ Stormwater BMP Manual)
 $c = 0.99$ (runoff coefficient for impervious)
 $Q = ciA = 0.99 \times 3.2 \times 0.25 = 0.79$ cfs

Given the site runoff is 0.79 cfs and based on Table A-1 below, the Barracuda™ MAX Model S3 with an MTFR of 0.85 cfs would be the smallest model that could be used for this site to remove 50% of the TSS from the impervious area without exceeding the MTFR.

The sizing table corresponding to the available system models is noted below. Additional specifications regarding each model can be found in the NJCAT Technology Verification Appendix under Tables A-1 and A-2.

Table A-1 Barracuda™ MAX HDS Models and Associated MTFRs

Model	Manhole Diameter (ft)	Maximum Treatment Flow Rate (cfs)	50% Maximum Sediment Storage Area Volume (ft³)
Barracuda MAX S3	3	0.85	5.89
Barracuda MAX S4	4	1.52	10.47
Barracuda MAX S5	5	2.37	16.36
Barracuda MAX S6	6	3.40	23.56
Barracuda MAX S8	8	6.08	41.89
Barracuda MAX S10	10	9.48	65.45

A detailed maintenance plan is mandatory for any project with a stormwater BMP subject to the Stormwater Management rules under N.J.A.C. 7:8. The plan must include all of the items identified in the Maintenance requirements section of the Stormwater Management rules under N.J.A.C. 7:8-5.8. Such items include, but are not limited to, the list of inspection and maintenance equipment and tools, specific corrective and preventative maintenance tasks, indication of problems in the system, and training of maintenance personnel. Additional information can be found in Chapter 8: Maintenance and Retrofit of Stormwater Management Measures.

If you have any questions regarding the above information, please contact Lisa Schaefer of my office at lisa.schaefer@dep.nj.gov.

Sincerely,

A handwritten signature in blue ink that reads "Gabriel Mahon". The signature is written in a cursive style with a large initial 'G'.

Gabriel Mahon, Chief
Bureau of NJPDES Stormwater Permitting & Water Quality Management

Attachment: Maintenance Plan

cc: Chron File
Richard Magee, NJCAT
Changi Wu, NJDEP-BFHSE
Madhu Guru, NJDEP - BFHSE

Barracuda[®] Max[™] & Barracuda Maintenance Guide

One of Barracuda's advantages is the ease of maintenance. Like any system that collects pollutants, the Barracuda must be maintained for continued effectiveness. Maintenance is a simple procedure performed using a vacuum truck or similar equipment. The systems were designed to minimize the volume of water removed during routine maintenance, reducing disposal costs.

Contractors can access the pollutants stored in the manhole through the manhole cover. This allows them to gain vacuum hose access to the bottom of the manhole to remove sediment and trash. There is no confined space entry necessary for inspection or maintenance.

The entire maintenance procedure typically takes 2 to 4 hours, depending on the system's size, the captured material, and the vacuum truck's capacity.

Local regulations may apply to the maintenance procedure. Safe and legal disposal of pollutants is the responsibility of the maintenance contractor. Maintenance should be performed only by a qualified contractor.

Inspection and Cleaning Cycle

Periodic inspection is needed to determine the need for and frequency of maintenance. You should begin inspecting as soon as construction is complete and then on an annual basis. Typically, the system needs to be cleaned every 1-3 years.

Excessive oils, fuels or sediments may reduce the maintenance cycle. Periodic inspection is important.

Determining When to Clean

To determine the sediment depth, the maintenance contractor should lower a stadia rod into the manhole until it contacts the top of the captured sediment and mark that spot on the rod. Then push the probe through to the bottom of the sump and mark that spot to determine sediment depth.


Maintenance should occur when the sediment has reached the levels indicated in the Storage Capacity Chart.

Barracuda Storage Capacities

Model	Manhole Diameter in. (mm)	Total System Volume Gallons (Liters)	Treatment Chamber Capacity Gallons (Liters)	Standard Sediment Capacity (20" depth) Yards ³ (meters ³)	NJDEP Sediment Capacity (50% of standard depth) Yards ³ (meters ³)
S3	36 (900)	264 (999)	212 (803)	0.44 (0.34)	0.22 (0.17)
S4	48 (1200)	665 (2517)	564 (2135)	0.78 (0.60)	0.39 (0.30)
S5	60 (1500)	1040 (3937)	881 (3335)	1.21 (0.93)	0.61 (0.47)
S6	72 (1800)	1497 (5667)	1269 (4804)	1.75 (1.34)	0.88 (0.67)
S8	96 (2400)	4196 (15884)	3835 (14517)	3.10 (2.37)	1.55 (1.19)
S10	120 (3000)	7976 (30192)	7496 (28375)	4.85 (3.71)	2.43 (1.86)

Maintenance Instructions

1. Remove the manhole cover to provide access to the pollutant storage. Pollutants are stored in the sump, below the bowl assembly visible from the surface. Access this area through the 8" (200 mm), 10" (250 mm), 15" (375 mm) or 20" (500 mm) diameter access cylinder.
2. Use a vacuum truck or other similar equipment to remove all water, debris, oils and sediment. See figure 1.
3. Use a high pressure hose to clean the manhole of all the remaining sediment and debris. Then, use the vacuum truck to remove the water.
4. Fill the cleaned manhole with water until the level reaches the invert of the outlet pipe.
5. Replace the manhole cover.
6. Dispose of the polluted water, oils, sediment and trash at an approved facility.
 - a. Local regulations prohibit the discharge of solid material into the sanitary system. Check with the local sewer authority for authority to discharge the liquid.
 - b. Some localities treat the pollutants as leachate. Check with local regulators about disposal requirements.
 - c. Additional local regulations may apply to the maintenance procedure.



Maintenance Guide

BaySaver Barracuda™

July 2017

One of the advantages of the BaySaver Barracuda is the ease of maintenance. Like any system that collects pollutants, the BaySaver Barracuda must be maintained for continued effectiveness. Maintenance is a simple procedure performed using a vacuum truck or similar equipment. The systems were designed to minimize the volume of water removed during routine maintenance, reducing disposal costs.

Contractors can access the pollutants stored in the manhole through the manhole cover. This allows them to gain vacuum hose access to the bottom of the manhole to remove sediment and trash. There is no confined space entry necessary for inspection or maintenance.

The entire maintenance procedure typically takes from 2 to 4 hours, depending on the size of the system, the captured material, and the capacity of the vacuum truck.

Local regulations may apply to the maintenance procedure. Safe and legal disposal of pollutants is the responsibility of the maintenance contractor. Maintenance should be performed only by a qualified contractor.

Inspection and Cleaning Cycle

Periodic inspection is needed to determine the need for and frequency of maintenance. You should begin inspecting as soon as construction is complete and thereafter on an annual basis. Typically, the system needs to be cleaned every 1-3 years.

Excessive oils, fuels or sediments may reduce the maintenance cycle. Periodic inspection is important.

Determining When to Clean

To determine the sediment depth, the maintenance contractor should lower a stadia rod into the manhole until it contacts the top of the captured sediment and mark that spot on the rod. Then push the probe through to the bottom of the sump and mark that spot to determine sediment depth.

Maintenance should occur when the sediment has reached the levels indicated in the Storage Capacity Chart.

BaySaver Barracuda Storage Capacities

Model	Manhole Diameter	Treatment Chamber Capacity	Standard Sediment Capacity (20" depth)	NJDEP Sediment Capacity (50% of standard depth)
S3	36"	212 gallons	0.44 cubic yards	0.22 cubic yards
S4	48"	564 gallons	0.78 cubic yards	0.39 cubic yards
S5	60"	881 gallons	1.21 cubic yards	0.61 cubic yards
S6	72"	1269 gallons	1.75 cubic yards	0.88 cubic yards
S8	96"	3835 gallons	3.10 cubic yards	1.55 cubic yards
S10	120"	7496 gallons	4.85 cubic yards	2.43 cubic yards

Maintenance Instructions

1. Remove the manhole cover to provide access to the pollutant storage. Pollutants are stored in the sump, below the bowl assembly visible from the surface. You'll access this area through the 10" diameter access cylinder.



2. Use a vacuum truck or other similar equipment to remove all water, debris, oils and sediment. See figure 1.
3. Use a high pressure hose to clean the manhole of all the remaining sediment and debris. Then, use the vacuum truck to remove the water.
4. Fill the cleaned manhole with water until the level reaches the invert of the outlet pipe.
5. Replace the manhole cover.
6. Dispose of the polluted water, oils, sediment and trash at an approved facility.
 - Local regulations prohibit the discharge of solid material into the sanitary system. Check with the local sewer authority for authority to discharge the liquid.
 - Some localities treat the pollutants as leachate. Check with local regulators about disposal requirements.
 - Additional local regulations may apply to the maintenance procedure.




Figure 1

Barracuda[®] Max & Barracuda Maintenance Guide

One of Barracuda's advantages is the ease of maintenance. Like any system that collects pollutants, the Barracuda must be maintained for continued effectiveness. Maintenance is a simple procedure performed using a vacuum truck or similar equipment. The systems were designed to minimize the volume of water removed during routine maintenance, reducing disposal costs.

Contractors can access the pollutants stored in the manhole through the manhole cover. This allows them to gain vacuum hose access to the bottom of the manhole to remove sediment and trash. There is no confined space entry necessary for inspection or maintenance.

The entire maintenance procedure typically takes 2 to 4 hours, depending on the system's size, the captured material, and the vacuum truck's capacity.

Local regulations may apply to the maintenance procedure. Safe and legal disposal of pollutants is the responsibility of the maintenance contractor. Maintenance should be performed only by a qualified contractor.

Inspection and Cleaning Cycle

Periodic inspection is needed to determine the need for and frequency of maintenance. You should begin inspecting as soon as construction is complete and then on an annual basis. Typically, the system needs to be cleaned every 1-3 years.

Excessive oils, fuels or sediments may reduce the maintenance cycle. Periodic inspection is important.

Determining When to Clean

To determine the sediment depth, the maintenance contractor should lower a stadia rod into the manhole until it contacts the top of the captured sediment and mark that spot on the rod. Then push the probe through to the bottom of the sump and mark that spot to determine sediment depth.


Maintenance should occur when the sediment has reached the levels indicated in the Storage Capacity Chart.

Barracuda Storage Capacities

Model	Manhole Diameter in. (mm)	Total System Volume Gallons (Liters)	Treatment Chamber Capacity Gallons (Liters)	Standard Sediment Capacity (20" depth) Yards ³ (meters ³)	NJDEP Sediment Capacity (50% of standard depth) Yards ³ (meters ³)
S3	36 (900)	264 (999)	212 (803)	0.44 (0.34)	0.22 (0.17)
S4	48 (1200)	665 (2517)	564 (2135)	0.78 (0.60)	0.39 (0.30)
S6	72 (1800)	1497 (5667)	1269 (4804)	1.75 (1.34)	0.88 (0.67)
S8	96 (2400)	4196 (15884)	3835 (14517)	3.10 (2.37)	1.55 (1.19)

Maintenance Instructions

1. Remove the manhole cover to provide access to the pollutant storage. Pollutants are stored in the sump, below the bowl assembly visible from the surface. Access this area through the 8" (200 mm), 10" (250 mm), 15" (375 mm) or 20" (500 mm) diameter access cylinder.
2. Use a vacuum truck or other similar equipment to remove all water, debris, oils and sediment. See figure 1.
3. Use a high pressure hose to clean the manhole of all the remaining sediment and debris. Then, use the vacuum truck to remove the water.
4. Fill the cleaned manhole with water until the level reaches the invert of the outlet pipe.
5. Replace the manhole cover.
6. Dispose of the polluted water, oils, sediment and trash at an approved facility.
 - a. Local regulations prohibit the discharge of solid material into the sanitary system. Check with the local sewer authority for authority to discharge the liquid.
 - b. Some localities treat the pollutants as leachate. Check with local regulators about disposal requirements.
 - c. Additional local regulations may apply to the maintenance procedure.



Appendix F: Construction Period Erosion Control Plan

Construction Period Erosion Control Plan

“Deer Meadow Way”

Project Location:

136 East Street
South Hadley, Massachusetts 01075
(Map 35, parcel 6)

Owner/Applicant:

136 East Street, LLC
c/o Mr. Gerald Coderre
383 Newton Street
South Hadley, Massachusetts 01075

RLA Project File: 250511

September 30, 2025

R LEVESQUE ASSOCIATES, INC
A LAND PLANNING SERVICES COMPANY

40 School Street · Westfield, MA 01085
p 413.568.0985 · f 413.568.0986 · www.rlaland.com



The project shall implement a construction period erosion control plan. The following provides descriptions and guidelines to ensure that the areas surrounding the project site will be protected from excessive sedimentation and runoff during construction.

1.1 Construction Period Pollution Prevention And Erosion Control Measures

1.1.1 Preconstruction Notifications And Meetings

Prior to the start of construction, the contractor shall call together a pre-construction meeting including a representative from the City, the design engineer, contractor, and any pertinent persons that should be in attendance. These requirements shall be the responsibility of the Contractor to arrange, attend, and document.

1.1.2 Sediment Barrier And Work Limit

Before installation of the sediment barriers, the location shall be staked in the field for review and approval by the owner or their representative. To facilitate sediment barrier installation, woody vegetation may then be removed and any required trench may be cut by machine, provided all other ground cover is left intact. No excavation, grading, filling, or removal of vegetative ground cover shall begin until sediment barriers have been installed as shown on the plans and have been inspected by the owner or their representative.

1.1.3 Silt Fence

The bottom of the fence shall be trenched into the ground a minimum of 6" and back-filled with compacted soil. Where trenching is not feasible, silt fence skirt shall be covered with compacted soil or crushed stone. The top of the fabric shall be stretched as tightly as is practical, with intermediate stakes added to correct excessive sags. Stakes shall be driven at least 12" into the ground. Splices between sections shall be made by rolling end stakes together one complete turn and driving into the ground together.

1.1.4 Straw Bales

Straw bales may be used as temporary and moveable control measures, temporary check dams, or as reinforcement for silt fence in areas of concentrated runoff or high fills. Bales shall be tightly butted and staked 12" into the ground. Where used without silt fence in front, the bales shall be trenched 4" into the ground, back-filled with compacted soil, and the spaces between bales shall be chinked with loose hay.

1.1.5 Filter Sock (Filtrex Or Equivalent)

In areas of expected sheet flow, filter sock may be placed directly on the ground without trenching or stakes. In areas of expected concentrated flow, mulch or crushed stone shall be placed along the up-slope face to control and filter underflow. Additional layers of Filter Sock may be required for adequate freeboard. The filter sock shall be staked at 10 feet on-center or in cases where they cannot be staked, utilize heavy concrete blocks to hold in place.

1.1.6 Temporary Sedimentation Basins

Temporary sediment basins may be excavations or bermed stormwater detention structures (depending on grading) that will retain runoff for a sufficient period of time to allow suspended soil particles to settle out prior to discharge. These temporary basins will be located based on construction needs as determined by the contractor and outlet devices will be designed to control velocity and sediment. Points of discharge from sediment basins will be stabilized to minimize erosion. If the temporary basin is to be located within an area of future infiltration as part of the stormwater management system, the excavation shall be limited to one foot above final grade of the infiltration structure.

1.1.7 Stocking Additional Materials

A stock of additional erosion control materials shall be available on the site for emergency repairs and temporary measures. Stock shall be replenished when decreased to 50% of the numbers below. Stock shall include:

Straw Bales – 10 (kept dry) with 20 oak stakes

Or

Silt Fence – 30 Linear feet.

Or

Filter Sock – 4 – 8 foot sections (kept dry)

Washed Stone – One (1) cubic yard, ¾" to 2" diameter

1.1.8 Trench Protection

Open trenches shall be protected from accumulation of surface water or groundwater that could result in erosion of the trench and discharge of sediment. Where feasible, spoil shall be stockpiled on the up-slope side of the trench to prevent entrance of surface runoff. Backfill shall be crowned to allow for settlement and to avoid concentration of runoff on top of the trench.

1.1.9 Site Stabilization – Temporary

Where a portion of the site will not be subject to construction activity for over 14 days, measures shall be taken to provide temporary stabilization of that inactive portion of the site, within 14 days of the cessation of construction activity. Stabilization measures may include seeding for temporary cover, mulching, or other measures to protect exposed soil from erosion and prevent sediment movement.

1.1.10 Site Stabilization – Permanent

Within 14 days of completion of loaming and finish grading on any portion of the site, that area shall be seeded or planted for permanent cover (season permitting) in accordance with USDA NRCS guidelines or equivalent.

1.1.11 Roadway Sweeping

The entrance to the site and affected portions of the access drive or paved project areas shall be swept as needed to control sediment runoff into storm drains or waterways and to control blowing dust.

1.2 Short-Term Erosion Control Maintenance

The following provides short-term erosion control maintenance guidelines and requirements.

1. The contractor or subcontractor will be responsible for implementing each control shown on the sedimentation and erosion control plan.
2. All erosion and sediment control devices shall be properly maintained during all phases of construction until the completion of all construction activities and all disturbed areas have been stabilized. Additional control measures will be installed during construction in order to control erosion and/or off-site sedimentation if deemed necessary by on-site inspection.
3. Effective erosion control measures shall be initiated prior to the commencement of clearing, grading, excavation, or other operations that will disturb the natural protection.
4. All sediment and erosion control devices shall be inspected at least once every seven (7) calendar days and after any storm event greater than 0.5 inches of precipitation during any 24-hour period, and the inspection shall be documented in writing. Damaged or ineffective devices shall be repaired or replaced, as necessary.
5. The contractor shall take all reasonable precautions to avoid excess erosion of the site due to the construction of this project.
6. Silt shall be removed from behind barriers if greater than 6-inches deep or as needed. Sediment that is collected in structures shall be disposed of properly and covered if stored on-site
7. Damaged or deteriorated items will be repaired immediately after identification.
8. All ditches shall be stabilized as soon as is practicable to minimize erosion.
9. The contractor shall maintain all erosion control devices in a good, working state of repair. Upon complete stabilization of any tributary areas, the erosion control devices shall be removed and disposed of so as to cause no off-site siltation.
10. Inspect and maintain construction entrance stone such that sediment does not track onto the street. Any sediment tracked onto the street shall be swept daily.
11. After catch basins have been constructed, the contractor shall protect the inlets by constructing inlet protection as shown on the plans.
12. Once the site has been paved, all catch basin inlets shall receive a silt sack type protection.
13. Erosion control measures shall remain in place until all disturbed earth has been substantially stabilized. After removal of structures, disturbed areas shall be regraded and stabilized as necessary.

Appendix G: Long-Term Operation and Maintenance Plan

- Long-Term Operation & Maintenance Plan Narrative
- StormTech Chamber Info Sheet
- Isolator Row O&M Manual
- Barracuda Concrete Installation Guide
- Barracuda Max Maintenance Guide
- O&M Checklist

Long-Term Operation & Maintenance Plan

“Deer Meadow Way”

Project Location:

136 East Street
South Hadley, Massachusetts 01075
(Map 35, parcel 6)

Owner/Applicant:

136 East Street, LLC
c/o Mr. Gerald Coderre
383 Newton Street
South Hadley, Massachusetts 01075

RLA Project File: 250511

September 30, 2025

R LEVESQUE ASSOCIATES, INC

A LAND PLANNING SERVICES COMPANY

40 School Street · Westfield, MA 01085
p 413.568.0985 · f 413.568.0986 · www.rlaland.com



I. Long-Term Stormwater Maintenance Program:

This Long-Term Operation and Maintenance Plan (O&M) identifies inspection and maintenance requirements for the proposed stormwater management system. The O&M references guidelines set forth by the Stormwater Management Handbook developed by the Massachusetts Department of Environmental Protection.

Owner/Responsible Party*:

136 East Street, LLC
c/o Mr. Gerald Coderre
383 Newton Street
South Hadley, Massachusetts 01075

*The party listed shall be responsible for implementation and record keeping of the requirements listed in this operation and maintenance plan. Upon sale of property or any other transition of ownership, the responsible party shall be reinstated as the new owner or any other group created as determined by the owner.

2. Inspection and Maintenance Program:

Regular inspection and routine maintenance are necessary to ensure that the stormwater management system continues to control and treat runoff. The following lists the inspection schedule and maintenance procedures for the proposed stormwater Best Management Practices:

BMP	Inspection Schedule	Maintenance Schedule	Maintenance Procedures
Bituminous Concrete Pavement	Four times per year	Twice per year	<ul style="list-style-type: none"> Roadway to be swept in March or April following snow melt and again in late November or early December to remove fallen leaves and debris.
Deep-Sump Catch Basins	Four times per year	Four times per year	<ul style="list-style-type: none"> Remove sediment once deposits reach one half the depth from the bottom sump to the lowest invert.
Stormwater Piping	Once per year	Once per year	<ul style="list-style-type: none"> Inspect pipe entrances in catch basins and manholes and remove any blockages.
Water Quality Unit*	As specified by the manufacturer	As specified by the manufacturer	<ul style="list-style-type: none"> Clean the unit using the method specified by the manufacturer. Vactor trucks are typically used to clean these units.
Subsurface Infiltration Basin	Twice per year	Twice Per year	<ul style="list-style-type: none"> Verify that the inlet structure has no accumulation of sediment.
Isolator Row(s)**	Every 6 months for the first year. Once per year thereafter	3 inches of accumulated sediment	<ul style="list-style-type: none"> Measure accumulated sediment depth. Once sediment reaches 3 inches, maintenance cleaning should be performed.
Flared End Section	Four times per year	As Needed	<ul style="list-style-type: none"> Remove any debris or vegetation around the flared end section such that flow out of the structure is not impeded.
Roof Leaders	Once per year	Once per year	<ul style="list-style-type: none"> Inspect downspout connections at grade and remove any blockages. Open and inspect cleanout locations and remove any blockages.
Level Spreader	Every six months during the first year. Annually thereafter.	As Needed	<ul style="list-style-type: none"> Remove sediment from the toe of slope and/or riprap voids. Repair gullies and reseed bare spots immediately.

*See attached Device Operation and Maintenance Guides

**See attached Maintenance Guide

See the attached Long-Term O&M Inspection Checklist for record keeping purposes.

3. Additional Long-Term Operation and Maintenance Items

The following is a list of additional operation and maintenance items to be implemented by the owner/governing group to maintain the features proposed in this project.

- A. Proper storage, use, and disposal of hazardous chemicals, including automobile fluids, pesticides, paints, solvents, etc. shall be required. Information should be provided on chemicals of concern, proper use, and disposal options. Recycling programs for used motor oil, antifreeze, and other products should be developed.
- B. Vehicle Washing. This management measure involves educating the owner on the water quality impacts of the outdoor washing of vehicles and how to avoid allowing polluted runoff to enter the storm drain system. Outdoor vehicle washing has the potential to result in high loads of nutrients, metals, and hydrocarbons which is conveyed by the detergent-rich water into storm drains.
- C. Recycling, spill prevention and response plans, and proper material storage and disposal of potentially hazardous materials shall be implemented. It will be the responsibility of the owner to contain and legally remove any materials that are spilled onsite. The use of dry floor cleaners and absorbent materials and limiting the use of water to clean pavement is encouraged. Care should be taken to avoid accidental disposal of hazardous materials.
- D. Provisions for storing trash and waste products shall be implemented. The waste materials shall be collected by the owner and all materials shall be properly disposed of.
- E. Requirements for routine inspections and maintenance of stormwater best management practices. Routine inspections shall be performed to ensure the correct functioning of stormwater best management practices. See the specific maintenance criteria for detail regarding inspections and maintenance frequency.
- F. Requirements for Storage and Use of Fertilizers, Herbicides, and Pesticides. Fertilizers, pesticides, herbicides, lawn care chemicals, or other leachable materials shall be used in accordance with the Lawn Care Regulations of the Massachusetts Pesticide Board, 33 CMR 10.03 (30,31), as amended, with manufacturer’s label instructions and all other necessary precautions to minimize adverse impacts on surface and groundwater. The storage of any such materials shall be within structure designed to prevent the escape of contaminated runoff or leachate.
- G. Provisions for prevention of illicit discharges to the stormwater management system shall be implemented. Any illicit discharges to the stormwater management system shall be prohibited. It will be the owner’s responsibility to ensure compliance with the legal disposal of all materials and containment/cleanup of any illicit discharges.
- H. Training for staff or personnel involved with implementation of the Long-Term Pollution Prevention Plan shall be required. The owner/governing group will be responsible for the implementation of the measures set forth in the Long-Term Pollution Prevention Plan. Documentation that personnel and owners involved with the implementation of the Long-Term Pollution Prevention Plan have been trained to conduct such tasks shall be documented.

4. Winter and Snow Conditions

The following is a list of additional operation and maintenance items to be implemented by the owner during winter and snow conditions.

- A. Snowfall shall be stored on the grassed areas surrounding the pavement areas, excluding any areas utilized for stormwater management practices. As needed, any snow that cannot be stored on site shall be trucked off site and disposed of properly.
- B. Winter road salt and/or sand use and storage restrictions shall be implemented based on any restrictions issued for the project. Sodium chloride for ice control shall be used at the minimum salt to sand ratio which is consistent with the Massachusetts Department of Environmental Protection's guidelines. Sodium chloride, calcium chloride, chemically treated abrasives or other chemicals used for the removal of ice and snow on roads/drives shall not be stored on site.

5. Public Safety Features

The proposed site design utilizes the following features which have been incorporated to ensure the safety of the public:

- A. Control and collection of stormwater runoff through positive drainage and curbing directing it towards the drainage inlets;
- B. Heavy-duty stormwater drain manhole covers and catch basin grates have been designed to withstand H₂O loading;
- C. Reduction of peak discharge rates from the site in the post-development condition as compared to the pre-developed conditions;
- D. Development and implementation of an Operations & Maintenance Plan to ensure the stormwater management system continues to function as designed.

6. Estimated Cost of Maintenance

The following budget was prepared as an estimate of inspection and maintenance costs for the stormwater management system. The budget is an estimate only as the costs may vary depending on the level of sediment accumulation and frequency of maintenance tasks required.

BMP Inspections	Number of Occurrences	Maintenance Cost	Number of Structures	Sum
Water Quality Unit	2/year	\$100	2	\$400
Catch Basin	4/year	\$30	4	\$480
Isolator Row	2/year	\$100	1	\$200
Subsurface Infiltration Basin	2/year	\$100	1	\$200
Level Spreader	2/year	\$50	2	\$200
Total Estimated Annual Cost of Inspections				\$1,480

BMP Maintenance	Number of Occurrences	Maintenance Cost	Number of Structures	Sum
Water Quality Unit	2/year	\$500	2	\$2,000
Catch Basin	4/year	\$50	4	\$800
Isolator Row	2/year	\$100	1	\$200
Subsurface Infiltration Basin	2/year	\$500	1	\$1,000
Level Spreader	1/year	\$600	2	\$1,200
Total Estimated Annual Cost of Maintenance				\$5,200

ADS® Barracuda® Concrete Installation Guide

ADS Barracuda Max & Barracuda S4, S6, S8 Concrete Installation Guide


This installation guide is reference for installing the Barracuda Max S4, S6, S8 Water Quality Units into a precast concrete structure in the field.



(1) Deflector Plate



(1) Center Funnel Extender












(2) A/C Stainless Steel
Tooth Set

(2) B/D Stainless Steel
Tooth Set



(1) Barracuda Max
Plastic Funnel

S4	 (4) Stainless Steel Funnel Mounting Flanges	 (1) Roll of Conseal®	 (16) Concrete Anchor ¼ x 2¼"
S6	 (4) Stainless Steel Funnel Mounting Flanges	 (3) Roll of Conseal®	 (16) Concrete Anchor ¼ x 2¼"
S8	 (8) Stainless Steel Funnel Mounting Flanges	 (4) Roll of Conseal®	 (22) Concrete Anchor ¼ x 2¼"

Please check that all components are on site. Below is a list of tools that may be required for installation.

- 1/4" Diameter Carbide Tipped Concrete Bit
- Standard Electrical or Battery Operated Drill
- Adjustable Wrench
- Marker for writing on the concrete wall
- Hammer Drill for Concrete (Fits the 1/4" Diameter Concrete Drill Bit)
- 7/16" Driver or deep socket for installation of provided ¼" Concrete Wedge Anchors
- Hammer
- Level
- Ladder that will extend to bottom of the structure
- Safety Glasses
- Hard Hat
- Protective Gloves
- Site Drawings
- ADS Design Layout

Installation Instructions (These directions assume the manhole base and riser have been assembled, but that the top slab/cone has not been set).

*Do not insert the inlet or outlet pipes until after the Barracuda Max internals have been installed. If pipes must be inserted in advance, the pipes should not protrude into the structure as they will interfere with installation of the bowl.

1. Install mounting flanges for the Barracuda Max plastic funnel. These flanges need to be installed at the same height, as indicated by model in Table 1. For example, the anchor holes for S4 flanges should be drilled 77" (1925 mm) from the sump floor. S4 and S6 models have four flanges and they need to be evenly spaced at 12, 3, 6, and 9 o'clock positions. S8 funnels require eight flanges that also need to be evenly spaced (i.e., forty-five degrees on a circle) around the inside of the manhole. This flange points are typically located in the third manhole section from the sump and also contain the pipe openings for the Barracuda Max unit. Use the same anchor procedure as you will when mounting the teeth (see step #4 below), using the ¼" (6.25 mm) concrete drill bit to drill 1¼" (31.25 mm) deep holes. Do not over drill the depth of the anchors. Lightly hammer the anchors in place and use locking nuts to firmly secure the flanges (Figure 1).
2. Next, mount the four sets of teeth vertically inside the manhole sump. Using the engineer's plans or the ADS layout, determine the correct orientation for the plastic funnel outlet hole in relation to the outlet pipe (Figures 2 and 5). The first set of teeth (marked as "A" on the teeth part) will be mounted under the center of the outlet hole from the Bowl. Mark that location with a plumb vertical line, this will serve as the "12 o'clock" landmark in the manhole (Figure 3). Repeat this process to mark lines at the 3, 6, and 9 o'clock positions for a total of four.
3. Each kit includes four sets of teeth. Two of these sets are stamped with the letters A and C. The other two sets are stamped B and D. The ADS shop drawing layout will label the teeth letters and all designs will be the A/B configuration (Figure 5). You will install each set of teeth in the correct location, with the indicated letter facing up (Figure 4). See Table 1 for the correct elevation for the top anchor location of each tooth set, measured from the sump floor for each Barracuda Max Unit. The teeth anchors are all at the same elevation. For example, for an S4 Barracuda the top anchor of an A or B indicated set of teeth will be 60" (1500 mm) off the sump floor. Mark the top anchor elevations on each of your four vertical lines (Figure 3), noting that A and B sets of teeth will be at the same height.



Figure 1



Figure 2



Figure 3





Figure 5

Figure 4



4. To fasten the sets of the teeth to the manhole, use the ¼" concrete drill bit and drill holes approximately 1¼" (31.25 mm) deep at your marked top anchor locations. Do not over drill into the concrete wall. Using a hammer, lightly tap the concrete anchors into the drilled holes (Figure 4). Hang the tooth set on the top anchor with the correct letter facing up and use a locking nut to loosely secure the tooth set to the wall (do not fully tighten the locking nut at this point). With the set of teeth hanging from the top anchor, line up and mark the bottom anchor location and drill the hole. Then hammer the bottom anchor in place and secure the teeth with a lock nut. Use an adjustable or socket wrench to tighten all the top and bottom locking nuts, except for the top nut on the outlet set of teeth (see step #5 below for the deflector plate installation, which will share the top anchor post), so that the teeth are firmly secured to the wall.
5. To attach the deflector plate to the concrete manhole you will use the exit tooth's top concrete anchor and share that linking point with the center tab of the deflector plate. Place the center tab of the deflector plate over the anchor bolt "post" on the outlet set of teeth and hand tighten the nut. Ideally, the plate will be held in place by this center point. Mark the location of the additional mounting tabs for the deflector plate while holding the plate relatively level. All deflector plate concrete anchors will be at the same elevation as the top tooth linking points and the anchors will be installed like the description in step #4. Once the two outer deflector plate linking points have been located, the installer can draw a vertical line and measure the exact location corresponding to the "high" teeth anchoring elevation. Once the deflector plate concrete anchors are installed tighten the nuts to complete the fastening of the deflector plate to the wall of the structure. See Figure 6 to show this more clearly.
6. Lower the plastic funnel into the structure (Figure 7), orienting the weir and outlet hole as depicted in the ADS layout (as identified in step 1). S6 and S8 units have eyebolts threaded holes on the top of the funnel to assist in lifting, and the eyebolts are provided in the equipment kit. If the eyebolts are misplaced, S6 units have ¾" (9 mm) -16 threads and S8 units utilize ½" (12 mm) -13 threads. After the bowl is in place, install the center funnel extender through the hole and seat it until the tabs of the extender touch the bowl itself (Figure 8). This is a friction-based attachment and no fasteners are needed.
7. Next, you'll use Conseal to fill any gaps around the funnel. S6 and S8 units are provided with a metal funnel plug. This plug is placed in the funnel opening for worker safety and must be utilized ANYTIME SOMEONE ENTERS THE STRUCTURE. Unroll the Conseal and wedge it between the funnel and manhole to create a seal (Figure 9). Conseal should also be used to seal between the vertical edges of the weir wall and the manhole. The plastic funnel can expand with high temperature. Install the funnel during cooler parts of the day, or keep the funnel shaded until installation can mitigate fitment issues. Once the Conseal is installed, the internal component installation is complete. The funnel plug may be discarded (if applicable), and the top slab can be set. If the application calls for a grated inlet, orient the slab so the grate is above the inlet (large bowl) side of the plastic funnel.

For maintenance details, please refer to the Barracuda Max Maintenance Manual. If the application requires a trash rack or oil boom, reference the appropriate supplementary installation instructions.



Figure 6



Figure 7



Figure 8




Figure 9

Table 1

	S4	S6	S8
Top Anchor Elevation from Sump Floor (A and B tooth indication)	60" (1270 mm)	68" (1475 mm)	90" (1880 mm)
Funnel Flange Anchor Elevation from Sump Floor	77" (1960 mm)	77" (1960 mm)	127" (3220 mm)

Note: Distances can be +/- 1-2 inches (25-50 mm) from these locations for the A, and B teeth, but flange elevations should be adhered to as much as possible and can only be lowered a maximum of 1 inch (25 mm) from these values listed above.

This guide is intended for field installations of Barracuda Max S4, S6, and S8 water quality units into precast manholes. For pre-casters installing internal components prior to job site delivery, contact ADS for possible modifications to component elevations.



Barracuda[®] Max & Barracuda Maintenance Guide

One of Barracuda's advantages is the ease of maintenance. Like any system that collects pollutants, the Barracuda must be maintained for continued effectiveness. Maintenance is a simple procedure performed using a vacuum truck or similar equipment. The systems were designed to minimize the volume of water removed during routine maintenance, reducing disposal costs.

Contractors can access the pollutants stored in the manhole through the manhole cover. This allows them to gain vacuum hose access to the bottom of the manhole to remove sediment and trash. There is no confined space entry necessary for inspection or maintenance.

The entire maintenance procedure typically takes 2 to 4 hours, depending on the system's size, the captured material, and the vacuum truck's capacity.

Local regulations may apply to the maintenance procedure. Safe and legal disposal of pollutants is the responsibility of the maintenance contractor. Maintenance should be performed only by a qualified contractor.

Inspection and Cleaning Cycle

Periodic inspection is needed to determine the need for and frequency of maintenance. You should begin inspecting as soon as construction is complete and then on an annual basis. Typically, the system needs to be cleaned every 1-3 years.

Excessive oils, fuels or sediments may reduce the maintenance cycle. Periodic inspection is important.

Determining When to Clean

To determine the sediment depth, the maintenance contractor should lower a stadia rod into the manhole until it contacts the top of the captured sediment and mark that spot on the rod. Then push the probe through to the bottom of the sump and mark that spot to determine sediment depth.


Maintenance should occur when the sediment has reached the levels indicated in the Storage Capacity Chart.

Barracuda Storage Capacities

Model	Manhole Diameter in. (mm)	Total System Volume Gallons (Liters)	Treatment Chamber Capacity Gallons (Liters)	Standard Sediment Capacity (20" depth) Yards ³ (meters ³)	NJDEP Sediment Capacity (50% of standard depth) Yards ³ (meters ³)
S3	36 (900)	264 (999)	212 (803)	0.44 (0.34)	0.22 (0.17)
S4	48 (1200)	665 (2517)	564 (2135)	0.78 (0.60)	0.39 (0.30)
S6	72 (1800)	1497 (5667)	1269 (4804)	1.75 (1.34)	0.88 (0.67)
S8	96 (2400)	4196 (15884)	3835 (14517)	3.10 (2.37)	1.55 (1.19)

Maintenance Instructions

1. Remove the manhole cover to provide access to the pollutant storage. Pollutants are stored in the sump, below the bowl assembly visible from the surface. Access this area through the 8" (200 mm), 10" (250 mm), 15" (375 mm) or 20" (500 mm) diameter access cylinder.
2. Use a vacuum truck or other similar equipment to remove all water, debris, oils and sediment. See figure 1.
3. Use a high pressure hose to clean the manhole of all the remaining sediment and debris. Then, use the vacuum truck to remove the water.
4. Fill the cleaned manhole with water until the level reaches the invert of the outlet pipe.
5. Replace the manhole cover.
6. Dispose of the polluted water, oils, sediment and trash at an approved facility.
 - a. Local regulations prohibit the discharge of solid material into the sanitary system. Check with the local sewer authority for authority to discharge the liquid.
 - b. Some localities treat the pollutants as leachate. Check with local regulators about disposal requirements.
 - c. Additional local regulations may apply to the maintenance procedure.



Project: _____

Responsible Party: _____

Address: _____

Date: _____

BPM Name: _____

Page: 1 of 1

Operation & Maintenance Inspection Checklist

BMP Element:	Potential Problem:	Resolution:	Pass	Fail	Recommended Remediation
Deep-Sump Catch Basins	Sediment has accumulated to a depth greater than the original design depth for sediment storage, approximately 2-feet of sediment.	Remove the sediment and dispose of in accordance with local and state regulations.			
Stormwater Piping	Blockage of inlet/outlet pipes due to debris or sediment accumulation.	Remove any debris and sediment via proper means. Dispose of debris/sediment in accordance with local & state regulations			
Roof Leaders	Downspout connections have been damaged or disconnected.	Repair and reconnect downspout connections.			
	Roof leaders are surcharging at the downspout connections	Open and inspect at cleanout locations and remove any blockages.			
Proprietary Treatment Device	Sediment has accumulated to a depth greater than the original design depth for sediment storage.	Remove sediment and disposed of in accordance with local and state regulations.			
Subsurface Infiltration Basin	Accumulation of sediment at the inlet structure above maintenance level.	Remove the sediment and conduct proper maintenance to the up-gradient pretreatment devices.			
Isolator Row	Accumulation of sediment over 3-inches within the isolator row.	Remove the sediment and conduct the proper maintenance per the Isolator Row Operation and Maintenance Manual.			
Flared End Sections	Vegetation has started to grow within the riprap area.	Remove vegetation immediately.			
	Accumulation of sediment/debris at the culvert inlet.	Remove sediment or debris such that the culvert has free flow.			
	Erosion is occurring where riprap has been dislodged.	Remedy scoured area and replace riprap immediately.			
Level Spreader	Sediment has accumulated in riprap channel void space.	Remove the sediment and dispose of in accordance with local and state regulations and replace riprap.			
	Down-gradient gullies have formed due to sheet flow concentration.	Fill gullies with native backfill, No. 6 pea-stone, topsoil and erosion control blanket. Sod or re-seed with stabilized erosion control grass mix.			

Inspector's Signature _____

Date _____

Appendix H: Illicit Discharge Compliance Statement

Illicit Discharge Compliance Statement

The owners of the land/responsible party will be responsible for prohibiting illicit discharges to the stormwater management system during construction and during its life of operation. The stormwater management system is comprised of the components for conveying, treating, and infiltrating stormwater runoff on-site, including stormwater best management practices and any pipes intended to transport stormwater to the groundwater, a surface water, or municipal separate storm sewer system. An illicit discharge shall constitute any connection or discharge to the stormwater management system including, but not limited to, wastewater discharges, discharge of stormwater contaminated by contact with process wastes, raw materials, toxic pollutants, hazardous substances, oil, or grease.

Responsible Party*:

136 East Street, LLC
c/o Mr. Gerald Coderre
383 Newton Street
South Hadley, Massachusetts 01075

*The party listed shall be responsible for implementation and record keeping of the requirements listed in this operation and maintenance plan. Upon sale of property or any other transition of ownership, the responsible party shall be reinstated as the new owner or any other group created as determined by the owner.

Signature of Responsible Party Representative

Date

Signature of Responsible Party Representative**

Date

**Required upon transfer of ownership

Appendix I: Low Impact Development Considerations

Low Impact Development Considerations

“Deer Meadow Way”

Project Location:

136 East Street
South Hadley, Massachusetts 01075
(Map 35, parcel 6)

Owner/Applicant:

136 East Street, LLC
c/o Mr. Gerald Coderre
383 Newton Street
South Hadley, Massachusetts 01075

RLA Project File: 250511

September 30, 2025

R LEVESQUE ASSOCIATES, INC

A LAND PLANNING SERVICES COMPANY

40 School Street · Westfield, MA 01085

p 413.568.0985 · f 413.568.0986 · www.rlaland.com



Introduction

Per the Massachusetts Stormwater Handbook, project proponents must consider environmentally sensitive site design and low impact development techniques to effectively manage stormwater. As a part of the proposed project, the proponent has considered a number of environmentally sensitive, low impact development techniques to prevent the generation of stormwater and non-point source pollution.

The following is a detailed description of the considerations for each low impact development measure. For ease of review, RLA has provided the consideration of each measure as detailed in the Massachusetts Stormwater Report Checklist.

Low Impact Development (Lid) Measures

1. Environmentally Sensitive Project Approach

The applicant is proposing to develop the locus property by constructing a condominium community and associated site improvements including a stormwater management system to mitigate the impacts of the proposed project. Site disturbance has been limited to the minimum areas required for site functionality.

2. No disturbance to any Wetland Resource Areas

All proposed site improvements are located outside of existing wetland resource areas. Portions of the proposed site improvements are located inside wetland buffer zones. Disturbance to existing wetland buffer zones has been reduced to functional minimums required for applicant needs and town requirements.

3. Site Design Practices (e.g. clustered development, reduced frontage setbacks)

This LID is not applicable for this project. The proposed project does not include any changes to existing property lines therefore no cluster or reduced frontage options are available.

4. Reduced Impervious Area (Redevelopment Only)

The proposed project is not part of a redevelopment project. Impervious areas have been reduced to functional minimums required for applicant needs and town requirements.

5. Minimizing disturbance to existing trees and shrubs

The proposed site improvements have been reduced to the minimums allowed by town requirements for the proposed project. Driveway widths and parking areas have been reduced to the minimum amounts required for functional accessibility based on town regulations. Demolition of existing trees and shrubs has been minimized to the extent practicable.

6. LID Site Design Credit Requested

No LID Site Design Credit is requested for the proposed project.

7. Use of "country drainage" versus curb and gutter conveyance and pipe

Country drainage conveyance requires a larger footprint than curb and gutter conveyance and creates areas with undulating terrain. Due to pre-existing constraints and limitations of the project site, country drainage was not utilized on this project.

8. Bioretention Cells (includes Rain Gardens)

Due to stormwater burdens from the 100-year storm event, a subsurface infiltration basin was determined to be the only BMP capable of meeting required town regulations.

9. Constructed Stormwater Wetlands (includes Gravel Wetlands designs)

Constructed stormwater wetlands require very specific design scenarios such as large tributary areas to support wetland characteristics and high groundwater elevations among others. The sub-catchment drainage area for this project site is not large enough to incorporate a constructed stormwater wetland.

10. Treebox Filter

The extensive costs associated with treebox filters, along with the climatic conditions of the area over the winter, present unique circumstances that would only provide a maintenance problem and a potential hazard for the owner. Treebox filters were not selected as a favorable stormwater BMP for this project.

11. Water Quality Swale

Water quality swales are best management practices that require a greater footprint of development in order to facilitate the grading of the swale. Due to the limited available pervious areas within the project site, water quality swales were not utilized.

12. Grass Channel

Grassed channels were utilized along the northern and southern property lines to convey water to, a detention pond (northern property line), or directly to the design point (southern property line).

13. Green Roof

Based on project size and scope, green roofs were not selected as a cost-effective BMP for this project.

14. Other

Please see the Stormwater Report for more information.