BENCHMARK INFORMATION

TBM 4
SPIKE IN 24" MAPLE
ELEV. = 136.72' ASSUMED

PROPOSED CB-2
RIM = 133.50
INV = 129.0

PROP. BIT. BERM

PROPOSED NEW PARKING LOT

GRASS STRIP

PROPOSED CB-1
RIM = 133.5
INV = 129.0

PROPOSED CB-3
RIM = 135.0
INV = 131.0

PROPOSED NEW DROP-OFF LANE

PROF. CURB

MIDDLE SCHOOL

MOSIER STREET

ELEMENTARY SCHOOL

100' BUFFER

50' BUFFER

4+00 5+00 6+00 7+00 8+00 9+00 10+00 11+00 12+00 12+80.75

BENCHMARK INFORMATION

TBM 1
TOP SPINDLE HYDRANT
ELEV. = 141.14' ASSUMED

TBM 2
SPIKE IN LIGHT POLE
ELEV. = 137.15' ASSUMED

TBM 3
SPIKE IN UTILITY POLE 8/12
ELEV. = 135.25' ASSUMED

MAGNETIC 2008

LEGEND

- SEWER MANHOLE
- DRAINAGE MANHOLE
- MANHOLE
- CATCH BASIN
- TELEPHONE MANHOLE
- ELECTRIC TRANSFORMER/MANHOLE/HANDHOLD
- UTILITY/LIGHT POLE
- HYDRANT
- WATER GATE/SPRINKLER VALVE
- GAS GATE/METER
- FLAGPOLE
- WETLAND FLAG
- MAILBOX
- SIGN
- BOUND
- POST/BOLLARD
- WILLOW
- MAPLE
- OAK
- FLOWERING CRABAPPLE
- PINE
- LOCUST
- CHERRY/WEEPING CHERRY
- DOGWOOD
- TREE LINE
- SHRUBS
- OVERHEAD WIRES
- FENCE
- DRAIN LINE
- SEWER LINE
- GAS LINE
- WATER LINE
- ELECTRIC LINE

NO.	DATE	MADE BY	CHECK'D BY	DESCRIPTION
1	7/1/09	YL		SHOW EXISTING 4 MAPLE TREES

REVISIONS

TOWN OF SOUTH HADLEY, MASSACHUSETTS
DEPARTMENT OF PUBLIC WORKS

SCALE: 1" = 40'

PROJECT NAME: xxx

DRAWING NAME: xxx

DRAWN BY: YEM LIP, P.E.

CHECKED BY: xxx

DATE: 07-01-09

MIDDLE SCHOOL: PARKING LOT EXPANSION

SITE PLAN

SHEET 2 OF 2